FINAL ENGINEERING PLANS FOR

LONG BEACH ROAD SIDEWALK PROGRAM

PLAN LEGEND

EXISTING	LINETYPES	PROPOSED
LAISTING	DRAIN TILE STORM SEWER SANITARY SEWER WATER MAIN (W/ SIZE) PIPE TRENCH BACKFILL GAS MAIN TELEPHONE LINES ELECTRIC LINE FENCE RIGHT-OF-WAY EASEMENT PROPERTY LINE SETBACK LINE	
680	CENTERLINE ————————————————————————————————————	680
• — 0 — 0 — 0 — 0 — 0 — 0 — 0 — 0 — 0 —	SANITARY MANHOLE STORM MANHOLE CATCH BASIN INLET SUMP STRUCTURE FIRE HYDRANT PRESSURE CONNECTION VALVE & VAULT, VALVE FLARED END SECTION STREET LIGHT UTILITY POLE CONTROL POINT SIGN SPOT ELEVATION	— ○ — ○ — • — • — • — • — • — • — × — • — × — • — ××.xx
	OVERLAND FLOW ROUTE — DRAINAGE SLOPE TREE, EVERGREEN, SHRUB & PROPOSED TREE TO REMOVE	— → — ※

PERMITS

AGENCY	DATE	PERMIT #

WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

WBK ENGINEERING, LLC


116 WEST MAIN STREET, SUITE 201, ST. CHARLES, ILLINOIS 60174 P: 630.443.7755 F: 630.443.0533 WWW.WBKENGINEERING.COM

PROFESSIONAL DESIGN FIRM NO. 184.007317

OSWEGO TOWNSHIP, ILLINOIS

WBK PROJECT NO. 21-0123

LOCATION MAP



SHEET INDEX

#	TITLE	DESCRIPTION	
1	CV1	COVER SHEET	
2	GN1	GENERAL NOTES	
3	SOQ	SUMMARY OF QUANTITIES	
4 - 8	ATB1 - ATB5	ALIGNMENT, TIES & BENCHMARKS	
9 - 13	RM1 - RM5	REMOVAL PLAN	
14 - 18	SP1 - SP5	SITE PLAN	
19 - 36	INT1 - INT14	INTERSECTION DETAILS	
37 - 38	SW1 - SW2	STORMWATER POLLUTION PREVENTION PLAN	
39- 40	EC1 - EC2	EROSION CONTROL DETAILS	
41	DT1	CONSTRUCTION DETAILS	
42 - 58	DOT1 - DOT15	IDOT HIGHWAY STANDARDS	

REVISIONS

ORIGIN	GINAL PLAN DATE:				
#	SHT NO.	DESCRIPTION			

CLIENT

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

CIVIL ENGINEER

ILLINOIS REGISTRATION NO.: 062-064196 EXPIRATION DATE: 11/30/2023

THESE PLANS OR ANY PART THEREOF SHALL BE CONSIDERED VOID WITHOUT THE SIGNATURE, SE AND EXPIRATION DATE OF SEAL OF THE ENGINEE

ENGINEER

VINCENT R. DI PRIMA, P.E.



SW, SE ¼ SECTION 4, TOWNSHIP 37N, RANGE 8E OSWEGO TOWNSHIP, UNINCORPORATED KENDALL COUNTY, ILLINOIS

EXPIRATION DATE: 04/30/2023

REFERENCED SPECIFICATIONS AND CODES

THE FOLLOWING DOCUMENTS SHALL GOVERN THE CONSTRUCTION OF THE PROPOSED IMPROVEMENTS, ALWAYS UTILIZING THE LATEST EDITION, IN CASE OF CONFLICT, THE MORE RESTRICTIVE PROVISION SHALL APPLY. THE CITED DOCUMENTS, COMBINED WITH THESE CONSTRUCTION PLANS AND ASSOCIATED PROJECT SPECIFICATIONS, ARE ALL TO BE CONSIDERED PART OF THE WORK. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE TO BE CONSIDERED PART OF THESE IMPROVEMENTS.

- THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (SSRBC) AND THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS.
- 2) THE ILLINOIS DEPARTMENT OF TRANSPORTATION "BUREAU OF LOCAL ROADS AND STREETS MANUAL", AS WELL AS ALL OTHER APPLICABLE CODES, DETAILS, SPECIFICATIONS, AND STANDARD PRACTICES OF ILLINOIS DEPARTMENT OF TRANSPORTATION
- 3) THE ILLINOIS SOCIETY OF PROFESSIONAL ENGINEERS "STANDARD SPECIFICATIONS FOR WATER AND SEWER CONSTRUCTION IN ILLINOIS".
- THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY "ILLINOIS URBAN MANUAL" (IUM).
- THE FEDERAL HIGHWAY ADMINISTRATION "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" (MUTCD).
- THE ILLINOIS ACCESSIBILITY CODE AND THE AMERICANS WITH DISABILITIES ACT.
- THE KENDALL COUNTY STORMWATER MANAGEMENT ORDINANCE AND ASSOCIATED TECHNICAL REFERENCE MANUAL, AS WELL AS ALL OTHER APPLICABLE CODES, ORDINANCES, DETAILS, SPECIFICATIONS, AND STANDARD PRACTICES OF KENDALL COUNTY.

GENERAL PROJECT NOTES

- 1) ALL CONTRACTORS ARE ADVISED TO VISIT THE SITE PRIOR TO SUBMITTING
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR SAFETY ON THE JOB. THE CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
- PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, GRADES AND CONDITIONS AFFECTING THE WORK WITH THE ACTUAL CONDITIONS AT THE JOB SITE, IF THERE ARE ANY DISCREPANCIES BETWEEN FIELD CONDITIONS AND WHAT IS SHOWN ON THE CONSTRUCTION PLANS, THEY MUST BE IMMEDIATELY REPORTED TO THE ENGINEER BEFORE ANY WORK BEGINS. FAILURE TO REPORT SUCH DIFFERENCES WILL RESULT IN THE CONTRACTOR HAVING BEEN DETERMINED TO PROCEED AT THEIR OWN RISK AND EXPENSE.
- 4) IN THE EVENT OF DISAGREEMENT BETWEEN THE CONSTRUCTION PLANS SPECIFICATIONS AND/OR PROJECT DETAILS, THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTION FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSIONS OR DISCREPANCIES. FAILURE TO REPORT SUCH DIFFERENCES WILL RESULT IN THE CONTRACTOR HAVING BEEN DETERMINED TO PROCEED AT THEIR OWN RISK AND EXPENSE
- 5) IN THE EVENT OF ANY DOUBT OR QUESTIONS ARISING WITH RESPECT TO THE TRUE MEANING OF THE CONSTRUCTION PLANS, SPECIFICATIONS AND/OR PROJECT DETAILS, THE DECISION OF THE ENGINEER SHALL BE FINAL AND CONCLUSIVE.
- THE CONTRACTOR SHALL DESIGNATE A JOB SUPERINTENDENT AT THE START OF CONSTRUCTION AND THE CONTRACTOR'S SUPERINTENDENT SHALL BE ON-SITE AT ALL TIMES DURING CONSTRUCTION, THE SUPERINTENDENT SHALL BE RESPONSIBLE FOR ENSURING THAT THE CONTRACTOR COMPLLIES WITH THE PROJECT PLANS AND SPECIFICATIONS.
- AS REQUIRED BY THE ENGINEER THE CONTRACTOR SHALL NOTIFY ALL TESTING AGENCIES AS CONTRACTED BY THE OWNER SUFFICIENTLY IN ADVANCE OF CONSTRUCTION. FAILURE TO NOTIFY SUCH AGENCIES RESULTING IN THE TESTING AGENCIES BEING UNABLE TO VISIT THE SITE WILL RESULT IN THE CONTRACTOR SUSPENDING OPERATIONS THAT PERTAIN TO TESTING UNTIL THE TESTING AGENCIES ARE PRESENT ON-SITE. ANY COSTS ASSOCIATED WITH THIS SUSPENSION OF WORK SHALL BE BORNE BY THE CONTRACTOR
- 8) AS REQUIRED BY THE ENGINEER, THE CONTRACTOR SHALL NOTIFY ALL EMERGENCY RESPONSE AGENCIES SUFFICIENTLY IN ADVANCE OF CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN VEHICULAR ACCESS FOR EMERGENCY VEHICLES AT ALL TIMES. AT NO TIME SHALL ACCESS TO BUILDINGS AND ROADWAYS WITHIN THE PROJECT LIMITS BE DENIED UNLESS SPECIFICALLY APPROVED BY THE ENGINEER.
- THE CONTRACTOR'S SUPERINTENDENT SHALL BE REQUIRED TO MAINTAIN IN THEIR POSSESSION AT ALL TIMES A COPY OF THE APPROVED ENGINEERING PLANS, SPECIFICATIONS AND ALL PROJECT PERMITS

GENERAL PROJECT NOTES (CONTINUED)

- 10) ANY EXISTING SIGNS, LIGHT STANDARDS OR UTILITY POLES WHICH INTERFERE WITH CONSTRUCTION OPERATIONS AND ARE NOT NOTED FOR REMOVAL SHALL BE KEPT OPERATIONAL AND MAINTAINED BY THE CONTRACTOR AT THEIR OWN EXPENSE. THIS SHALL INCLUDE THE TEMPORARY REMOVAL, RELOCATION AND/OR RESETTING OF SUCH ITEMS AS DIRECTED BY THE ENGINEER. ANY DAMAGE TO THESE ITEMS SHALL BE REPAIRED BY THE CONTRACTOR AT THEIR OWN EXPENSE TO THE SATISFACTION OF THE ENGINEER AND/OR OWNER. ANY ITEMS THAT ARE NOT TO BE RESET SHALL BE DELIVERED TO THEIR RESPECTIVE OWNER.
- 11) THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR THE PROPER BRACING. SHORING AND ANY OTHER REQUIRED PROTECTION OF ALL ROADWAYS BEFORE THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES FAILURE TO PROVIDE PROTECTION RESULTING IN DAMAGES TO EXISTING ROADWAYS. SIDEWALKS, CURBS, UTILITY STRUCTURES AND OTHER PUBLIC INFRASTRUCTURE WILL REQUIRE THE CONTRACTOR TO MAKE REPAIRS AT THEIR OWN EXPENSE TO THE SATISFACTION OF THE ENGINEER.
- 12) THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL BENCHMARKS, SECTION OR SUBSECTION MONUMENTS, PROPERTY CORNERS. AND REFERENCE MARKERS UNTIL THE OWNER OR THE OWNER'S REPRESENTATIVE HAS WITNESSED OR OTHERWISE REFERENCED THEIR
- 13) THE CONTRACTOR SHALL NOT DELIVER AND STORE ANY MATERIALS ON THE PROJECT SITE MORE THAN SEVEN (7) DAYS IN ADVANCE OF COMMENCING WORK. ALL STORAGE LOCATIONS MUST BE APPROVED IN ADVANCE BY THE ENGINEER, STORAGE LOCATIONS THAT FALL OUTSIDE THE PROJECT LIMITS WILL NOT BE ALLOWED. NO PORTION OF THE ROADWAY MAY BE USED FOR MATERIAL STORAGE AT ANY POINT DURING CONSTRUCTION.
- 14) ALL REPAIRS AND/OR REPLACEMENTS TO THE PARKWAY, PAVEMENT, CURBS, SIDEWALKS ETC. AS A RESULT OF DAMAGE DUE TO MATERIAL STORAGE ACTIVITIES SHALL BE COMPLETED AT THE CONTRACTOR'S OWN EXPENSE.
- 15) THE ENGINEER WILL INSPECT ALL WORK PRIOR TO FINAL APPROVAL. FINAL PAYMENT TO THE CONTRACTOR WILL NOT BE MADE UNTIL ALL WORK HAS BEEN APPROVED AND CERTIFIED COMPLETE BY THE ENGINEER.

EXISTING UTILITIES

- 1) IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONFIRM OR ESTABLISH THE EXISTENCE OF ALL EXISTING UTILITY FACILITIES AND THEIR EXACT LOCATIONS. PRIOR TO COMMENCEMENT OF SITE DITURBING ACTIVITIES, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 1-800-892-0123 FOR FIELD LOCATION OF BURIED UTILITIES, A MINIMUM 48-HOUR NOTIFICATION PERIOD IS REQUIRED.
- 2) IF EXISTING UTILITY LINES OF ANY NATURE ARE ENCOUNTERED WHICH CONFLICT WITH LOCATIONS OF THE PROPOSED IMPROVEMENTS, THE CONTRACTOR MUST IMMEDIATELY NOTIFY THE ENGINEER.
- 3) TO THE BEST OF OUR KNOWLEDGE, EASEMENTS FOR THE EXISTING UTILITIES, BOTH PUBLIC AND PRIVATE, AND UTLITIES LOCATED WITHIN THE PUBLIC RIGHT-OF-WAY ARE SHOWN ON THE PLANS IN ACCORDANCE WITH AVAILABLE RECORDS
- 4) THE CONTRACTOR SHALL NOTIFY EXISTING UTILITY COMPANIES AT LEAST 72 HOURS PRIOR TO THE START OF ANY OPERATION REQUIRING COOPERATION
- 5) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES EVEN IF THEY ARE NOT SHOWN ON THE PLANS UTILITIES THAT ARE DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED TO THE SATISFACTION OF THE OWNER OR REPLACED AT THE CONTRACTOR'S OWN EXPENSE
- 6) THE CONTRACTOR SHALL USE ALL NECESSARY PRECAUTIONS AND PROTECTION MEASURES REQUIRED TO MAINTAIN EXISTING UTILITIES, SEWERS AND APPURTENANCES THAT MUST BE KEPT IN OPERATION.
- 7) THE CONTRACTOR SHALL COOPERATE WITH ALL UTILITY COMPANIES INVOLVED WITH THE REMOVAL, TEMPORARY RELOCATION, SUPPORT, PROTECTION, RECONSTRUCTION OR ABANDONMENT BY THESE COMPANIES OF ANY AND ALL SERVICES OR FACILITIES OWNED OR OPERATED BY THEM WITHIN THE PROJECT LIMITS.

EXCAVATION, PROPOSED UTILITIES AND SITE GRADING

- 1) THE CONTRACTOR IS RESPONSIBLE FOR ALL CONSTRUCTION STAKING AND SHALL PROVIDE FIELD ENGINEERING SERVICES TO PERFORM SUCH WORK.
- 2) THE CONTRACTOR IS RESPONSIBLE FOR ALL AS-BUILT SURVEY AND SHALL PROVIDE FIELD ENGINEERING SERVICES TO PERFORM SUCH WORK.
- 3) THE CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION LAYOUT STAKES UNTIL THEY ARE NO LONGER NEEDED. ANY STAKES DESTROYED OR DISTURBED BY THE CONTRACTOR PRIOR TO THEIR USE SHALL BE RESET BY THE CONTRACTOR AT THEIR OWN EXPENSE.
- 4) THE CONTRACTOR SHALL IMMEDIATELY REPORT TO THE ENGINEER CONDITIONS THAT MAY CAUSE UNSOUND REARING TO THE OWNER
- IN THE EVENT THAT UNSTABLE/SOFT MATERIALS ARE ENCOUNTERED, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER. THE DECISION TO REMOVE SAID MATERIALS, AND TO WHAT EXTENT, SHALL BE MADE BY THE
- 6) CONTRACTOR SHALL NOTICY ENGINEER IF THERE ARE ANY DISCREPANCIES BETWEEN FIELD CONDITIONS AND WHAT IS SHOWN ON THE CONSTRUCTION PLANS, THEY MUST BE IMMEDIATELY REPORTED TO THE ENGINEER BEFORE ANY WORK BEGINS. FAILURE TO REPORT SUCH DIFFERENCES WILL RESULT IN THE CONTRACTOR HAVING BEEN DETERMINED TO PROCEED AT THEIR OWN RISK AND EXPENSE.
- 7) THE CONTRACTOR SHALL WORK BASED ON THEIR OWN EXPLORATIONS AND OBSERVATIONS TO DETERMINE CONDITIONS AT THE LOCATION OF THE PROPOSED WORK
- 8) THE ELEVATIONS SHOWN ON THE CONSTRUCTION PLANS ARE TO FINISHED GRADE UNLESS OTHERWISE NOTED
- STATIONS AND OFFSETS SHOWN ON THE CONSTRUCTION PLANS FOR UTILITY STRUCTURES ARE TO THE CENTER OF THE STRUCTURE. RIM ELEVATIONS SHOWN FOR UTILITY STRUCTURES ARE TO PAVEMENT/FINISHED GRADE ELEVATION. STATIONS AND OFFSETS SHOWN FOR FLARED END SECTIONS ARE TO THE TOP MID-POINT OF THE TOE OF THE FLARED END SECTION.
- 10) DUE TO SPACE CONSTRAINTS, IT IS REQUIRED THAT TOPSOIL WILL BE REMOVED FROM THE SITE AND DISPOSED OF AT AN OFF-SITE LOCATION. THE CONTRACTOR SHALL NOT BE ALLOWED TO STRIP, STOCKPILE AND RESPREAD EXISTING TOPSOIL ON THE SITE. THE REMOVAL OF EXISTING TOPSOIL SHALL BE PAID FOR AS "EARTH EXCAVATION".
- 11) THE CONTRACTOR SHALL ONLY BE PAID FOR EARTHWORK ONCE REGARDLESS OF STAGING AND HOW MANY TIMES THE EXCAVATED MATERIALS ARE HANDLED. HANDLING OF EXCAVATED MATERIALS MORE THAN ONCE TO BETTER FACILITATE CONSTRUCTION ACTIVITIES SHALL BE DONE AT THE CONTRACTOR'S EXPENSE.
- 12) ALL EXCAVATION AND EMBANKMENT LOCATIONS SHALL BE CONSTRUCTED TO FOUR (4) INCHES BELOW FINISHED GRADE TO ALLOW FOR PLACEMENT OF TOPSOIL MATERIALS.
- 13) THE SUB-GRADE SHALL BE GRADED TO WITHIN A TOLERANCE OF 0.1 FEET OF THE PLAN SUBGRADE ELEVATIONS.
- 14) FILL MATERIALS SHALL NOT BE PLACED OVER EXISTING TOPSOIL OR OTHER UNSUITABLE MATERIALS UNLESS SPECIFICALLY APPROVED BY THE ENGINEER.
- 15) THE CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE DURING CONSTRUCTION AND PREVENT WATER FROM RUNNING INTO OR STANDING IN EXCAVATED AREAS. IF ADDITIONAL WORK IS REQUIRED DUE TO THE CONTRACTOR'S FAILURE TO FACILITATE POSITIVE DRAINAGE DURING CONSTRUCTION, SUCH WORK SHALL BE COMPLETED AT THE CONTRACTOR'S OWN EXPENSE.
- 16) IN THE EVENT THAT WATER ENTERS AN EXCAVATION, THE CONTRACTOR SHALL REMOVE SUCH WATER IN A TIMELY MANNER TO PREVENT SOFTENING AND OTHER SOIL CHANGES DETRIMENTAL TO SUBGRADE STABILITY. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN PUMPS, SUMPS, DISCHARGE LINES AND OTHER NECESSARY COMPONENTS TO MAINTAIN A DEWATERING SYSTEM TO CONVEY WATER AWAY FROM EXCAVATIONS AS DIRECTED BY THE ENGINEER

TOPOGRAPHIC SURVEY

- 1) THE HORIZONTAL DATUM IS NAD 83 AND THE VERTICAL DATUM IS NAVD 88.
- THE TOPOGRAPHIC SURVEY FOR THIS PROJECT WAS COMPLETED ON MARCH 14, 2021 BY WBK ENGINEERING, LLC. SUPPLEMENTAL PROJECT SURVEYS WERE COMPLETED ON FEBRUARY 16, 2022 BY WBK ENGINEERING, LLC.

SOIL EROSION AND SEDIMENT CONTROL

- ALL SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES SHALL BE IN ACCORDANCE WITH THE PROJECT SWPPP AND ALL PROJECT PERMITTING REQUIREMENTS, ALL PRE-CONSTRUCTION DEVICES AND MEASURES MUST BE IN PLACE PRIOR TO THE START OF SOIL-DISTURBING CONSTRUCTION ACTIVITIES.
- 2) THE CONTRACTOR SHALL MAINTAIN ALL STREETS, DRIVEWAYS, PARKING AREAS AND RIGHTS-OF-WAY FREE OF MUD, SOIL AND CONSTRUCTION DEBRIS. THE CONTRACTOR SHALL CLEAN STREETS OF THESE ITEMS AS DIRECTED BY THE ENGINEER OR AT THE END OF EACH WORKING DAY AT A
- 3) NO CONSTRUCTION EQUIPMENT OR VEHICLES SHALL BE STORED, SERVICED, WASHED OR FLUSHED IN A LOCATION WHERE LEAKS, SPILLAGE WASTE MATERIALS, CLEANERS OR WASHWATERS WILL BE INTRODUCED INTO OR FLOW DIRECTLY INTO STORM SEWER SYSTEMS OR WATERCOURSES.
- 4) THE CONTRACTOR SHALL MONITOR WEATHER FORECASTS AND IMMEDIATELY REMOVE ALL EQUIPMENT (INCLUDING ANY FUEL, EXPLOSIVES OR OTHER HAZARDOUS MATERIAL) FROM FLOOD PRONE AREAS IN THE EVENT OF ISSUANCE OF ANY FLOOD WATCHES OR WARNINGS.
- 5) AT THE END OF EACH WORKING DAY, THE CONTRACTOR SHALL REMOVE ANY LOOSE MATERIAL THAT HAS BEEN DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES, DITCHES OR GUTTERS SUCH THAT THE FLOW OF WATER IS NOT IMPEDED. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES SHALL BE CLEANED OF ALL DIRT AND DEBRIS PRIOR TO FINAL PROJECT INSPECTION.
- 6) ALL SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED IN GOOD WORKING ORDER THROUGHOUT THE DURATION OF CONSTRUCTION, DAMAGED OR INFEFECTIVE DEVICES AND MEASURES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER WITHIN A PERIOD OF 24 HOURS.
- 7) THE CONTRACTOR SHALL NOT REMOVE ANY SOIL EROSION AND SEDIMENT CONTROL DEVICES OR MEASURES FROM OPERATION UNTIL DIRECTED TO DO SO BY THE ENGINEER.

PERMITS

THE FOLLOWING PERMITS ARE REQUIRED FOR THIS PROJECT. ALL PERMITS MUST BE ISSUED AND IN HAND PRIOR TO COMMENCEMENT OF CONSTRUCTION.

1) ILLINOIS ENVIRONMENTAL PROTECTION AGENCY NPDES ILR10 PERMIT - NOTICE OF INTENT (NOI)

REMOVALS

- ITEMS SPECIFIED FOR REMOVAL SHALL BE LEGALLY DISPOSED OF OFF-SITE BY THE CONTRACTOR AT THEIR OWN EXPENSE. THE CONTRACTOR SHALL IDENTIFY AND COMMUNICATE TO THE ENGINEER ALL LOCATIONS THAT ARE TO BE UTILIZED FOR SUCH DISPOSAL.
- THE CONTRACTOR SHALL COLLECT AND REMOVE ALL CONSTRUCTION DEBRIS, EXCESS MATERIALS, TRASH, OIL AND GREASE RESIDUE, MACHINERY, TOOLS AND OTHER MISCELLANEOUS ITEMS WHICH WERE NOT PRESENT PRIOR TO THE COMMENCEMENT OF CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ANY AND ALL PERMITS NECESSARY FOR THE HAULING AND DISPOSAL OF DELETERIOUS MATERIALS AS REQUIRED BY THE ENGINEER.
- 3) ITEMS SPECIFIED FOR REMOVAL SUCH AS PAVEMENTS, DRIVEWAYS, SIDEWALKS, CURBS, ETC. SHALL BE CUT WITH A PAVEMENT SAW PRIOR TO REMOVAL. SAW CUTS SHALL BE MADE AT THE REMOVAL LIMITS OF THE ITEM BEING REMOVED AS MARKED BY THE ENGINEER.
- 4) THE CONTRACTOR SHALL NOT DAMAGE, REMOVE OR OTHERWISE IMPACT ITEMS NOT SPECIFIED FOR REMOVAL ON THE PROJECT PLANS UNLESS SPECIFICALLY APPROVED BY THE ENGINEER. IN THE EVENT THAT AN ITEM IS DAMAGED OR REMOVED. THE CONTRACTOR SHALL RESTORE THE ITEM TO IT'S ORIGINAL CONDITION AT THEIR OWN EXPENSE.

LONG BEACH ROAD SIDEWALK PROGRAM

GENERAL NOTES

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, L 116 WEST MAIN STREET, SUITE 2 ST. CHARLES, ILLINOIS 60174 (630) 443-7755



PROJECT NO. 21-0123 DATE: 03/28/2022

DRAWING NO. GN1 SHEET

SUMMARY OF QUANTITIES


TEM NO.	IDOT CODE	ITEM	QUANTITY	UNIT
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	66
3 28000510 INLET FILTERS		INLET FILTERS	EACH	20
4	42400800	DETECTABLE WARNINGS	SQ FT	493
5	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	718
6	44000300	CURB REMOVAL	FOOT	106
7	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	688
8	44000600	SIDEWALK REMOVAL	SQ FT	17,717
9	60600605	CONCRETE CURB, TYPE B	FOOT	106
10	67100100	MOBILIZATION	L SUM	1
11	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	1,848
12	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	346
13	X0326806	WASHOUT BASIN	L SUM	1
14	X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	788
15	X2600012	REMOVE AND RELOCATE SIGN PANEL AND POLE ASSEMBLY	EACH	21
16	X4230710	PCC DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	421
17	X4230800	PCC DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	79
18	X4240430	PCC SIDEWALK 5 INCH, SPECIAL	SQ FT	22,860
19	X4240440	PCC SIDEWALK 6 INCH, SPECIAL	SQ FT	3,786
20	X4240460	PCC SIDEWALK 8 INCH, SPECIAL	SQ FT	733
21	X6026624	VALVE BOX TO BE ADJUSTED (SPECIAL)	EACH	2
22	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
23	XX002053	LANDSCAPE RESTORATION	SQ YD	1,166
24	XX006520	AGGREGATE DRIVEWAY, 6 INCH	SQ YD	8
25	XX009224	CLASS D PATCHES, SPECIAL	SQ YD	157
26	Z0004530	HMA DRIVEWAY PAVEMENT, 8 INCH	SQ YD	47
27	Z0013798	CONSTRUCTION LAYOUT	L SUM	1
28	-	COMBINATION CONCRETE CURB AND GUTTER, SPECIAL	FOOT	688
		1		
		1		
			,	
	1	I .		





PROJECT NO. 21-0123


DATE: 03/28/2022

DRAWING NO. **SOQ1**










OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

PROJECT NO. 21-0123 DATE: 03/28/2022 DRAWING NO. ATB4



DATE ::


OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543


WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755





PROJECT NO. 21-0123 DATE: 03/28/2022


DRAWING NO. ATB5















13 OF 58


REMOVAL PLAN











- 2 6 4 3 9 7 8 OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

E. LONG BEACH ROAD SIDEWALK PROGRAM

SITE PLAN


WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755





PROJECT NO. 21-0123 DATE: 03/28/2022


DRAWING NO. SP5


SHEET 18 OF 58
































		[[
POINT	STATION	OFFSET	ELEVATION		
1	100+25.73	2.14' LT.	665.72	EX. ELEV	
2	100+32.25	0.37' LT.	665.69		
 3	100+39.57	0.00	665.40		
4	100+45.21	0.00	665.37		
5	100+49.47	0.00	665.48		
6	100+49.47	5.93' LT.	665.40	EX. ELEV	
7	100+49.52	7.52' LT.	665.27	EX. ELEV	(LOW POINT)

W

INTERSECTION DETAILS LONG BEACH ROAD SIDEWALK PROGRAM 665.35 665.45 665.36 EX. ELEV. 665.12 EX. ELEV. 665.24 LONG BEACH ROAD Q Η G - 0.49% 10 - 2.49% 11 2.55% 2.26% **EX ROW EX ROW** 5 PR BASELINE LONG 2.75% BEACH ROAD (TYP) 2.60% 15 3 ` 0 NOTES SEE STANDARD DETAILS 424011 & 424016 FOR 0.36% M CURB RAMPS FOR SIDEWALKS, RAMP'S RUNNING В N 2 SIDE CURB CROSS AND LANDING AREA SLOPES. THE DETECTABLE (TYP.) WARNING MUST BE INSTALLED A MAXIMUM OF 8" OR 1 Α LESS FROM THE FACE OF DEPRESSED CURB. 1.03% STATION OFFSET **ELEVATION** POINT POINT STATION **OFFSET ELEVATION** PADDOCK STREE 14WBK SINE ENGINE ENGINE 92+86.51 7.77' LT. 665.25 8 100 + 45.215.88' LKT 665.29 92+92.45 6.38' LT. 665.32 100+45.21 7.57' LT. 665.30 Κ 92+92.45 7.93' LT. 665.33 100 + 39.575.78' LT. 665.32 10 92+96.76 7.77' LT. 665.39 EX. ELEV. L 11 100 + 39.577.43' LT. 665.33 M 92+96.72 6.26' LT. 665.62 EX. ELEV. 12 100 + 32.867.48' LT. 665.37 EX. ELEV 92+99.28 6.18' LT. 665.58 EX. ELEV. Ν 6.11' LT. 13 100 + 32.76665.65 EX. ELEV 100 + 00PROJECT NO. 21-0123 Ο 92+97.07 22.59' LT 665.77 EX. ELEV. 100 + 28.536.13' LT. 665.68 EX. ELEV 14

15

16

100+35.18

100 + 38.45

23.17' LT.

25.33' LT

665.77

665.76

EX. ELEV.

Q

92+93.71

92+81.22

24.94' LT.

7.54' LT.

665.76

665.12

EX. ELEV

EX. ELEV.

(LOW POINT)


DRAWING NO. INT10


DATE: 03/28/2022


30 OF 58


EX. ELEV


EX. ELEV














THIS STORMWATER POLLUTION PREVENTION PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10 ISSUED BY THE ILLINOIS ENVIRONMENTAL

PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES. THE PERMIT IS ISSUED AND EFFECTIVE FROM AUGUST 3, 2018 AND IT EXPIRES ON JULY 31, 2023. THE PLAN CONSISTS OF THE SWPPP NARRATIVE AND NOTES, THE SWPPP PLAN SHEETS, INCLUDING ON AND OFF-SITE CONTROLS AND THE SWPPP DETAILS. THIS PLAN IS ONLY COMPLETE WHEN THE COMPONENT PARTS ARE INCLUDED.

1. SITE DESCRIPTION:

- A. THE WORK UNDER THIS CONTRACT WILL BE COMPLETED WITHIN THE RIGHT-OF-WAY FOR LONG BEACH ROAD.
- THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF THE MAJOR ACTIVITIES WHICH WILL DISTURB SOIL FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE:

 a. INSTALL PREVENTATIVE EROSION CONTROL MEASURES INCLUDING INLET FILTERS.
- REMOVE CURB & GUTTER: CURB: SIDEWALK: AND DRIVEWAYS.
- CONSTRUCT CURB AND GUTTER AND CURB.
- EXCAVATE FOR WIDENED SIDEWALK AND CONSTRUCT SIDEWALK
- **EXCAVATE FOR DRIVEWAYS AND CONSTRUCT DRIVEWAYS**
- RESTORE ALL AREAS OF DISTURBANCE WITH TOPSOIL, SEED, AND EROSION CONTROL BLANKET.
- REMOVE ALL TEMPORARY EROSION CONTROL MEASURES FROM THE SITE.
- THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.0 ACRES. THE TOTAL AREA OF THE SITE THAT IS ESTIMATED TO BE DISTURBED BY EXCAVATION, GRADING OR OTHER ACTIVITIES IS 1.0 ACRES.
- THE ESTIMATED RUNOFF COEFFICIENT FOR THE PROJECT IS 0.3 FOR EXISTING CONDITIONS AND 0.3 FOR THE PROPOSED PROJECT.
- THE SITE DRAINS BY OVERLAND FLOW INTO A STORM SEWER WHICH IS DIRECTLY TRIBUTARY TO FOX RIVER. THERE ARE 0.0 ACRES OF WETLANDS ONSITE.

2. CONTROLS

THIS SECTION OF THE PLAN ADDRESSES THE VARIOUS CONTROLS THAT WILL BE IMPLEMENTED FOR EACH OF THE MAJOR CONSTRUCTION ACTIVITIES DESCRIBED IN 1.B ABOVE. FOR EACH MEASURE DISCUSSED, THE CONTRACTOR WILL BE RESPONSIBLE FOR ITS IMPLEMENTATION AS INDICATED. EACH CONTRACTOR HAS SIGNED THE REQUIRED CERTIFICATION ON FORMS WHICH ARE ATTACHED TO AND ARE A PART OF THIS PLAN. THE SOIL FROSION AND SEDIMENT CONTROL PLAN DRAWINGS INCLUDED, DEFINE THE SIZE AND LOCATION OF THE MEASURES TO BE INSTALLED DURING THE CONSTRUCTION OF THIS PROJECT.

SOIL EROSION AND SEDIMENT CONTROLS a. STABILIZATION PRACTICES:

PROVIDED BELOW IS A DESCRIPTION OF INTERIM AND PERMANENT STABILIZATION PRACTICES INCLUDING SITE-SPECIFIC SCHEDULING OF THE IMPLEMENTATION OF THE PRACTICES. SITE PLANS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. A RECORD OF THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR, WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE, AND WHEN STABILIZATION MEASURES ARE INITIATED ARE INCLUDED IN THE PLAN. EXCEPT AS PROVIDED IN 2.A.a AND 2.B, STABILIZATION MEASURES SHALL BE PERFORMED ON A DAILY BASIS WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED ON ANY PORTION OF THE SITE AND WILL NOT RESUME FOR A PERIOD EXCEEDING 14 CALENDAR DAYS. STABILIZATION OF DISTURBED AREAS MUST BE INITIATED WITHIN 1 WORKING DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES AND SHALL BE COMPLETED AS SOON AS POSSIBLE BUT NOT LATER THAN 14 DAYS FROM THE INITIATION OF STABILIZATION WORK IN AN AREA. WHERE THE INITIATION OF STABILIZATION MEASURES IS PRECLUDED BY SNOW COVER, STABILIZATION SHALL BE INITIATED AS SOON AS PRACTICABLE, DESCRIPTION OF STABILIZATION PRACTICES:

- DUST CONTROL WILL BE ACCOMPLISHED USING WATERING TRUCKS AS DIRECTED BY THE ENGINEER.
- SEDIMENT TRACK-OUT WILL BE CONTROLLED THROUGH SWEEPING, SHOVELING, OR VACUUMING PAVED SURFACES OUTSIDE OF THE SITE BY THE END OF THE SAME BUSINESS DAY IN WHICH THE TRACK-OUT OCCURS.
- STOCKPILES THAT ARE TO REMAIN IN PLACE FOR MORE THAN THREE (3) DAYS SHALL HAVE SOIL EROSION AND SEDIMENT CONTROL PROVIDED. AT A MINII PERIMETER EROSION BARRIER WILL BE PLACED AROUND THE BOTTOM OF THE STOCKPILE AT NO COST TO THE TOWNSHIP
- STOCKPILES THAT ARE TO REMAIN FOR MORE THAN 14 CALENDAR DAYS SHALL RECEIVE TEMPORARY SEED AT NO COST TO THE TOWNSHIP

b. STRUCTURAL PRACTICES:

PROVIDED BELOW IS A DESCRIPTION OF STRUCTURAL PRACTICES THAT WILL BE IMPLEMENTED. TO THE DEGREE ATTAINABLE. TO DIVERT FLOWS FROM EXPOSED SOILS. STORE FLOWS, LIMIT RUNOFF AND THE DISCHARGE OF POLLUTANTS FROM EXPOSED AREAS OF THE SITE, STRUCTURAL PRACTICES WILL BE PLACED ON UPLAND SOILS TO THE DEGREE PRACTICABLE. THE INSTALLATION OF THESE DEVICES MAY BE SUBJECT TO SECTION 404 OF THE CLEAN WATER ACT.

PROVIDED BELOW IS A DESCRIPTION OF MEASURES THAT WILL BE INSTALLED DURING THE CONSTRUCTION PROCESS TO CONTROL THE POLLUTANTS IN STORM WATER DISCHARGES THAT WILL OCCUR AFTER THE CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED. THE INSTALLATION OF THESE DEVICES MAY BE SUBJECT TO SECTION 404 OF THE CLEAN WATER ACT

- a. THE PRACTICES SELECTED FOR IMPLEMENTATION WERE DETERMINED ON THE BASIS OF TECHNICAL GUIDANCE CONTAINED IN THE IEPA'S ILLINOIS URBAN MANUAL AND OTHER ORDINANCES LISTED IN THE SPECIFICATIONS. THE STORM WATER POLLUTANT CONTROL MEASURES SHALL INCLUDE:
- INLET FILTERS
- PERMANENT SEEDING WITH EROSION CONTROL BLANKET
- VELOCITY DISSIPATION DEVICES WILL BE PLACED AT DISCHARGE LOCATIONS AND ALONG THE LENGTH OF ANY OUTFALL CHANNEL AS NECESSARY TO PROVIDE A NON-EROSIVE VELOCITY FLOW FROM THE STRUCTURE TO A WATER COURSE SO THAT THE NATURAL PHYSICAL, AND BIOLOGICAL CHARACTERISTICS AND FUNCTIONS ARE MAINTAINED PROTECTED (I.E., MAINTENANCE OF HYDROLOGIC CONDITIONS, SUCH AS THE HYDROPERIOD AND HYDRODYNAMICS PRESENT PRIOR TO THE INITIATION OF CONSTRUCTION ACTIVITIES). STORM WATER MANAGEMENT CONTROL INCLUDES:
- N/A

C. OTHER CONTROLS

a. NON HAZARDOUS WASTE DISPOSAL: THE SOLID WASTE MATERIALS INCLUDING TRASH CONSTRUCTION DEBRIS, EXCESS CONSTRUCTION MATERIALS, MACHINERY, TOOLS AND OTHER ITEMS WILL BE COLLECTED AND DISPOSED OF OFF-SITE BY THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE TO ACQUIRE ANY PERMIT REQUIRED FOR SUCH DISPOSAL. BURNING ON-SITE WILL NOT BE PERMITTED. NO SOLID MATERIALS. INCLUDING BUILDING MATERIALS SHALL BE DISCHARGED INTO WATERS OF THE U.S., EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT

- HAZARDOUS WASTE STORAGE & DISPOSAL: SHALL CONFORM TO THE IDOT SPECIAL PROVISION AND BE IN ACCORDANCE WITH APPLICABLE STATE AND FEDERAL REGULATIONS
- SANITARY WASTE DISPOSAL: THE PROVISIONS OF THIS PLAN SHALL ENSURE AND DEMONSTRATE COMPLIANCE WITH THE APPLICABLE STATE AND/OR LOCAL WASTE DISPOSAL, SANITARY SEWER, OR SEPTIC SYSTEM REGULATIONS. THE CONTRACTOR SHALL NOT CREATE OR ALLOW UNSANITARY CONDITIONS. SEPARATE AUTHORIZATION IS REQUIRED FOR INSTALLATION OF SANITARY SEWER OR SEPTIC SYSTEMS.

 OFF-SITE VEHICLE TRACKING: EACH SITE SHALL HAVE ONE OR MORE STABILIZED
- CONSTRUCTION ENTRANCES IN CONFORMANCE WITH THE PLAN DETAILS. WHERE THE CONTRACTOR'S EQUIPMENT IS OPERATED ON ANY PORTION OF THE TRAVELED SURFACE OR STRUCTURES USED BY TRAFFIC ON OR ADJACENT TO THE PROJECT. THE CONTRACTOR SHALL CLEAN (NOT FLUSHING OF) THE TRAVELED SURFACE OF ALL DITT AND DEBRIS AT THE END OF EACH DAY'S OPERATIONS OR MORE FREQUENTLY IF DIRECTED BY THE ENGINEER.
- DEWATERING DEVICES: IF DEWATERING DEVICES ARE USED, DISCHARGE LOCATIONS SHALL BE PROTECTED FROM SOIL EROSION. ALL PUMPED DISCHARGES SHALL BE ROUTED THROUGH A SUMP PIT INTO A SEDIMENT BASIN. ALL SUMPED DISCHARGES TO WATERS OF THE US SHALL BE PERMITTED BY THE USACE.
- SITE CLEANUP: TRAPPED SEDIMENT AND OTHER DISTURBED SOILS RESULTING FROM THE DISPOSITION OF TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER SOIL FROSION AND SEDIMENTATION
- TREATMENT CHEMICALS: POLYMER FLOCCULANTS OR TREATMENT CHEMICALS SHALL BE USED FOR REDUCING TURBIDITY IN STORM WATER RUNOFF AND MINIMIZING EROSION ALL TREATMENT CHEMICALS SHALL BE STORED IN AREAS WHERE THEY WILL NOT BE EXPOSED TO PRECIPITATION AND WILL ONLY BE USED BY STAFF WHO ARE PROPERLY TRAINED.

APPROVED COUNTY, STATE & LOCAL PLANS:

THE MANAGEMENT PRACTICES, CONTROLS, AND OTHER PROVISIONS CONTAINED IN THIS PLAN ARE AT LEAST AS PROTECTIVE AS THE REQUIREMENTS CONTAINED IN THE CURRENT VERSION OF ILLINOIS ENVIRONMENTAL PROTECTION AGENCY'S ILLINOIS URBAN MANUAL STANDARDS AND SPECIFICATIONS. PROCEDURES AND REQUIREMENTS SPECIFIED IN APPLICABLE SOIL EROSION AND SEDIMENT CONTROL PLANS OR STORM WATER MANAGEMENT PLANS APPROVED BY LOCAL OFFICIALS SHALL BE DESCRIBED OR INCORPORATED BY REFERENCE BELOW. REQUIREMENTS SPECIFIED IN SOIL EROSION AND SEDIMENT CONTROL PLANS, SITE PERMITS, STORM WATER MANAGEMENT SITE PLANS, OR SITE PERMITS APPROVED BY COUNTY, STATE OR LOCAL OFFICIALS THAT ARE APPLICABLE TO PROTECTING SURFACE WATER RESOURCES ARE, UPON SUBMITTAL OF A NOTICE OF INTENT (NOI), INCORPORATED AND ENFORCEABLE UNDER THIS PERMIT EVEN IF THEY ARE NOT SPECIFICALLY INCLUDED IN THE PLAN. THE SOIL EROSION AND SEDIMENT CONTROL FOR THIS SITE MUST MEET THE REQUIREMENTS OF THE FOLLOWING AGENCIES:

OSWEGO TOWNSHIP & KENDALL COUNTY

3. MAINTENANCE:

THE FOLLOWING IS A DESCRIPTION OF PROCEDURES THAT WILL BE USED TO MAINTAIN, IN GOOD AND EFFECTIVE OPERATING CONDITIONS, VEGETATION, SOIL EROSION AND SEDIMENT CONTROL MEASURES, AND OTHER PROTECTIVE MEASURES IDENTIFIED IN THIS PLAN AND STANDARD SPECIFICATIONS. THE CONTRACTOR WILL ASSIGN A SOIL FROSION AND SEDIMENT CONTROL MANAGER (SESCM) TO THE PROJECT. HIS DUTIES WILL BE TO SUPERVISE THE MAINTENANCE OF THE SOIL EROSION AND SEDIMENT CONTROL MEASURES AND IMPLEMENTATION OF THIS PLAN.

THE FOLLOWING SHALL BE THE MINIMUM MAINTENANCE REQUIRED:

- A. VEGETATIVE SOIL EROSION MEASURES THE VEGETATIVE GROWTH OF TEMPORARY AND PERMANENT SEEDING, VEGETATIVE FILTERS, ETC., SHALL BE MAINTAINED PERIODICALLY AND SUPPLIED ADEQUATE WATERING AND FERTILIZER. THE VEGETATIVE COVER SHALL BE REMOVED AND RESEEDED AS NECESSARY
- B. WATER TREATMENT SYSTEM WILL BE CLEANED AND ITEMS REPLACED AS RECOMMENDED BY THE DESIGNER OF THE SYSTEM. SEDIMENT ACCUMULATION WILL BE REMOVED AT A MINIMUM WHEN THE HEIGHT IS EQUAL TO 50% OF THE HEIGHT OF THE BAFFLE OR CURTAIN.
- C. PERIMETER EROSION BARRIER AND ROLLED EXCELSIOR LOGS WILL BE EXAMINED REGULARLY AND REPAIRED AS NECESSARY. SEDIMENT SHALL BE REMOVED WHEN IT REACHES A HEIGHT EQUAL TO 50% OF THE HEIGHT OF THE BARRIER.
- D. STABILIZED ACCESS ROAD AND STABILIZED CONSTRUCTION ENTRANCES SHALL HAVE SEDIMENT BUILD UP REMOVED AS NECESSARY.

THE ENGINEER WILL BE RESPONSIBLE FOR CONDUCTING SOIL EROSION AND SEDIMENT CONTROL INSPECTIONS. THE CONTRACTOR'S SESCM SHALL BE NOTIFIED WHEN THE INSPECTIONS ARE TO TAKE PLACE AND IS EXPECTED TO BE PRESENT DURING THE INSPECTIONS. A MAINTENANCE INSPECTION REPORT WILL BE COMPLETED AFTER EACH INSPECTION. A COPY OF THE REPORT IS TO BE COMPLETED BY THE INSPECTOR AND STORED ON-SITE WITH A COPY GIVEN TO THE CONTRACTOR THE INSPECTION SHALL INCLUDE ALL DISTURBED AREAS OF THE CONSTRUCTION SITE WHICH HAVE NOT BEEN FINALLY STABILIZED. THE STRUCTURAL CONTROL MEASURES, LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE, AND ALL MAJOR OUTFALLS, SUCH INSPECTION SHALL BE CONDUCTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A RAIN STORM (OR FOLIVALENT SNOWFALL) THAT IS 0.5 INCHES OR GREATER. DEPTH OF RAIN FALL WILL BE DETERMINED BY AN ON-SITE RAIN GAUGE. THE ENGINEER SHALL READ THE RAIN GAUG DAILY AND AFTER EACH RAIN STORM.

- INSPECTIONS MAY BE REDUCED TO ONCE PER MONTH WHEN CONSTRUCTION ACTIVITIES HAVE CEASED DUE TO FROZEN CONDITIONS. WEEKLY INSPECTIONS WILL RECOMMENCE WHEN CONSTRUCTION ACTIVITIES ARE CONDUCTED, OR IF THERE IS 0.5" OR GREATER RAIN EVENT, OR A DISCHARGE DUE TO SNOWMELT OCCURS.
- B. AREAS INACCESSIBLE DURING INSPECTIONS DUE TO FLOODING OR UNSAFE CONDITIONS SHALL BE INSPECTED WITHIN 72 HOURS OF BECOMING ACCESSIBLE.
 C. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO
- PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM AND WATERWAYS. SOIL EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY. IF REPAIR IS NECESSARY, IT WILL BE INITIATED WITHIN 24 HOURS OF THE COMPLETION OF THE INSPECTION REPORT. WHERE DISCHARGE LOCATIONS OR POINTS ARE ACCESSIBLE, THEY SHALL BE INSPECTED TO ASCERTAIN WHETHER THE MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF-SITE TRACKING
- D. BASED ON THE RESULTS OF THE INSPECTION, THE DESCRIPTION OF POTENTIAL POLLUTANT SOURCES IDENTIFIED IN SECTION 1 ABOVE AND POLLUTION PREVENTION MEASURES IDENTIFIED IN SECTION 2 ABOVE, THE STORM WATER POLLUTION PREVENTION PLAN SHALL BE REVISED AS APPROPRIATE AS SOON AS PRACTICABLE AFTER SUCH INSPECTION. ANY CHANGES TO THIS PLAN RESULTING FROM THE REQUIRED INSPECTION SHALL BE IMPLEMENTED WITHIN SEVEN CALENDAR DAYS FOLLOWING THE INSPECTION.
- E. A REPORT SUMMARIZING THE SCOPE OF THE INSPECTION, NAME(S) AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION, THE DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THIS STORM WATER POLLUTION PREVENTION PLAN. AND ACTION TAKEN IN ACCORDANCE WITH SECTION 4.B SHALL BE MADE AND RETAINED AS PART OF THE PLAN FOR AT LEAST THREE YEARS AFTER THE DATE OF

INSPECTION. THE REPORT SHALL BE SIGNED IN ACCORDANCE WITH PART VI.G OF THE GENERA PERMIT.

IF ANY VIOLATIONS OF THE PROVISIONS OF THIS PLAN ARE IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION WORK COVERED BY THIS PLAN, THE ENGINEER SHALL COMPLETE AND FILE AN "INCIDENCE OF NONCOMPLIANCE" (ION) REPORT FOR THE IDENTIFIED VIOLATION. THE ENGINEER SHALL USE FORMS PROVIDED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY AND SHALL INCLUDE SPECIFIC INFORMATION ABOUT THE CAUSE OF NONCOMPLIANCE, ACTIONS WHICH WERE TAKEN TO PREVENT ANY FURTHER CAUSES OF NONCOMPLIANCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE. THE IEPA MUST BE NOTIFIED BY PHONE FAX OR E-MAIL WITHIN 24 HOURS OF THE DISCOVERY OF THE NONCOMPLIANCE ACTION. THE ION REPORT MUST BE FILED WITHIN 5 DAYS OF THE INCIDENT. ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI.G OF THE GENERAL PERMIT. THE REPORT OF NONCOMPLIANCE SHALL BE MAILED TO THE FOLLOWING

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL

1021 NORTH GRAND AVENUE EAST

P.O. BOX 19276 SPRINGFIELD, IL 62794-9276

epa.swnoncomp@illinois.gov

5. NON-STORM WATER DISCHARGES:

EXCEPT FOR THE FLOWS FROM FIRE FIGHTING ACTIVITIES. SOURCES OF NON-STORM WATER THAT MAY BE COMBINED WITH STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY ARE TREATED BY THE MEASURES INCLUDED IN THESE PLANS. THESE SOURCES INCLUDE THE FOLLOWING

- FIRE HYDRANT FLUSHING
- WATER USED TO WASH VEHICLES WHERE DETERGENTS ARE NOT USED.
- WATER USED TO CONTROL DUST
- POTABLE WATER SOURCES INCLUDING UNCONTAMINATED WATERLINE FLUSHING
- LANDSCAPE IRRIGATION DRAINAGES
- ROLITINE EXTERNAL BUILDING WASHDOWN WHICH DOES NOT USE DETERGENTS
- PAVEMENT WASH WATERS WHERE SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED (UNLESS SPILLED MATERIALS HAVE BEEN REMOVED) AND WHERE DETERGENTS ARE NOT USED
- UNCONTAMINATED AIR CONDITIONING CONDENSATE
- UNCONTAMINATED GROUND WATER
- FOUNDATION OR FOOTING DRAINS WHERE FLOWS ARE NOT CONTAMINATED WITH PROCESS MATERIALS SUCH AS SOLVENTS

6. INVENTORY FOR POLITION PREVENTION PLAN:

HE MATERIALS OR SUBSTANCES LISTED BELOW ARE EXPECTED TO BE PRESENT ON SITE DURING CONSTRUCTION. (TABLE TO BE FILLED IN BY CONTRACTOR.

-

SPILL PREVENTION - MATERIAL MANAGEMENT PRACTICES:

THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT WILL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES TO

THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ON SITE DURING THE CONSTRUCTION PROJECT

- AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCTS REQUIRED TO DO
- ALL MATERIALS STORED ON SITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER
- PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL
- MANUFACTURER'S LABEL.
 PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL MANUFACTURER'S LABEL
- SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE MANUFACTURER THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND
- DISPOSAL OF MATERIALS ON SITE.
- WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE DISPOSING OF THE CONTAINER. MANUFACTURERS' RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE

HAZARDOUS PRODUCTS:

THESE PRACTICES ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS:

- PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE.
- ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED
- IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURERS OR LOCAL AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE FOLLOWED

SPILL CONTROL PRACTICES:

IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP

- MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.
- MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ON SITE. EQUIPMENT AND MATERIALS WILL INCLUDE, BUT NOT RELIMITED TO BROOMS DUST PANS MOPS RAGS GLOVES GOGGLES KITTY LITTER, SAND, SAWDUST, AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALL FOR THIS PURPOSE.
- ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.
- THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH HAZARDOUS SUBSTANCES.

POST-CONSTRUCTION STORMWATER MANAGEMENT

THE FOLLOWING MEASURES SHALL BE INSTALLED DURING THE CONSTRUCTION PROCESS TO CONTROL POLLUTANTS IN STORM WATER DISCHARGES THAT WILL OCCUR AFTER CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED. THE INSTALLATION AND MAINTENANCE OF THESE MEASURES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE INSTALLATION OF THESE DEVICES MAY BE SUBJECT TO SECTION 404 OF THE CWA. THE MEASURES ARE AS FOLLOWS:

PERMANENT SEEDING WITH EROSION CONTROL BLANKET

ADDITIONAL EROSION AND SEDIMENT NOTES

- UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE ILLINOIS URBAN MANUAL (LATEST EDITION)
- A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- PRIOR TO COMMENCING LAND-DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT NOT LIMITED TO ADDITIONAL PHASES OF DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS) A SUPPLEMENTARY EROSION CONTROL PLAN SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL.
- THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE ENGINEER
- DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO SEDIMENT BASINS OR SILT TRAPS. WHEN DISCHARGING FROM THE SEDIMENT BASIN. UTILIZE OUTLET STRUCTURES THAT WITHDRAW WATER FROM THE SURFACE IN ORDER TO MINIMIZE DISCHARGE. PREVENT EROSION OF THE SEDIMENT BASIN USING STABILIZATION CONTROLS AT THE INLET AND OUTLET USING EROSION CONTROLS AND VELOCITY DISSIPATION DEVICES. SEDIMENT BASINS SHALL BE DESIGNED TO FACILITATE MAINTENANCE, INCLUDING SEDIMENT REMOVAL FROM THE BASINS. AS NECESSARY, DEWATERING DIRECTLY INTO FIELD TILES OR STORMWATER STRUCTURES IS STRICTLY PROHIBITED.
 IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO INFORM ANY SUB-
- CONTRACTOR(S) WHO MAY PERFORM WORK ON THIS PROJECT, OF THE REQUIREMENTS IN IMPLEMENTING AND MAINTAINING THESE EROSION CONTROL PLANS AND THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT REQUIREMENTS SET FORTH
- ALL DISTURBED AREAS SHALL BE COVERED IN AN ACCEPTABLE OR APPROVED TYPE OF PERMANENT SEEDING UNLESS OTHERWISE INDICATED.
- WHERE WORK IS COMPLETED, PERMANENT STABILIZATION SHALL OCCUR WITHIN SEVEN (7) DAYS OF COMPLETION, WHERE WORK HAS TEMPORARILY CEASED FOR FOURTEEN (14) DYAS OR MORE, TEMPORARY STABILIZATION SHALL OCCUR BY THE 7TH DAY AFTER WORK HAS
- ALL ADJACENT STREETS AND PARKING LOTS MUST BE KEPT CLEAR OF DEBRIS. INSPECTED DAILY AND CLEANED WHEN NECESSARY.
- CONCRETE WASHOUT LOCATIONS SHOULD BE DRAWN ON THESE PLANS BY THE CONTRACTOR AT TIME OF INSTALLATION. WASHOUTS ARE TO BE CONSTRUCTED AND MAINTAINED BY THE CONTRACTOR IN A MANNER CONSISTENT WITH THE LATEST VERSION OF THE ILLINOIS URBAN
- STOCKPILE LOCATIONS SHOULD BE DRAWN ON THESE PLANS BY THE CONTRACTOR AT TIME OF INSTALLATION. STOCKPILES MAY NOT BE LOCATED WITHIN THE LIMITS OF THE

LONG BEACH ROAD SIDEWALK PROGRAM

STORMWATER POLLUTI

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, L 116 WEST MAIN STREET, SUITE 2 ST. CHARLES, ILLINOIS 60174 (630) 443-7755



PROJECT NO. 21-0123 DATE: 03/28/2022 DRAWING NO. SW1

37 OF 58

SHEET

TRANSPORONY SEEDING PERSUMBET SEEDING SOCIOURS PERSUMBET SEEDING SOCIOURS PLANTE THEES, A SHRUBS SOCIOURS MALCHING MAL	CONTROL MEASURE GROUP	CONTROL MEASURE	APPL.	ΚΕ	CONTROL MEASURE CHARACTERISTICS	TEMP.	PERM
SEQUENT RECEIVED OPERATOR SEEDING OPERATOR SEEDING WAS SEED SEED SOUTH SEED SECRET COUNTY OF SEPTIMENTS OPERATOR SEEDING WAS SEED SEED SOUTH SEED SEED SOUTH SEED SEED SOUTH SEED SEED SOUTH SEED SEED SEED SOUTH SEED SEED SOUTH SEED SEED SOUTH SEED SEED SEED SEED SEED SEED SEED SEE		TEMPORARY SEEDING		TS			
MIGHER PROBLEMS SEED APPLICATION ARE RECOURSED.		PERMANENT SEEDING	X	PS			\times
SODOING DUMPA TERMANENT COVERT TO CHATTACL ERROSED, GUICK WAY TO ESTABLISH WHITE SECREDAL MY BE STEPPICLE. PLANTS, TREES, & SIRRUBS DIVERSIONS MALCHING MACCHING		DORMANT SEEDING	X	DS			\times
PLANTS, TREES, & SIRRUISS (CC) WISSETTATION, MAY BE USED AD PART OF A FINAL LANGSCAPE PLAN A COME WITH IN ADMINISTRATION OF THE PLAN AND PART OF A FINAL LANGSCAPE PLAN A COME WITH IN ADMINISTRATION OF THE PLAN AND PART OF A FINAL LANGSCAPE PLAN A COME WITH IN ADMINISTRATION OF THE PLAN AND PART OF TH	SOIL COVER	SODDING		(SO)	VEGETATION FILTER STRIP. CAN BE USED ON STEEP SLOPES OR IN DRAINAGEWAYS		
MUCCHING (W) CONTROLS INVANATION PROFITATION AND PRESERVES MOSTURE. PROVIDES DOVER MONOY VEGETATIVE SOLICOVER AGGREGATE COVER AGGREGATE COVER AGGREGATE COVER AGGREGATE COVER AGGREGATE COVER AGGREGATE COVER PAVINS (D) PAVINS (D) RIDGE DIVERSION (E) COMPANIS (D) PROVIDES SIGL EXCUSE ON ROADS AND PARRING LOTS AND AREAS SYMERE ADMINISTRY OF PROVIDES SIGL EXCUSE ON ROADS AND PARRING LOTS AND AREAS SYMERE AND PROVIDES SIGL EXCUSE ON ROADS AND PARRING LOTS AND AREAS SYMERE PAVINS (D) PROVIDES PERINANENT COVER ON RADAD PARRING LOTS AND ROADS OR OTHER AREAS PROVIDES SIGL EXCUSE ON ROADS AND PARRING LOTS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD PARRING LOTS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SANDER LOTS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SANDER LOTS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER AREAS (D) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER AREAS (E) PROVIDES SIGNAL AREAS AND ROADS AND ROADS OR OTHER AREAS (E) PROVIDES SIGNAL AREAS AND ROADS AND ROADS OR OTHER AREAS (E) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER TO DIVERT (E) PROVIDES PERINANENT COVER ON RADAD SOLEDS AND ROADS OR OTHER AREAS (E) PROVIDES SIGNAL AREAS ON A PARRING LOTS ON HOT SOLEDS TO DIVERS (E) PROVIDES SIGNAL AREAS ON A PARRING PERINANCE OR OTHER PROVIDES TO DIVERS (E) PROVIDES SIGNAL AREAS ON A PARRING COVER PROVIDED AND ROADS OF TABLE TY TO CHANNEL AND ROAD		PLANTS, TREES, & SHRUBS		(CC)	VEGETATION. MAY BE USED AS PART OF A FINAL LANDSCAPE PLAN ALONG WITH SHRUBS AND TREES.		
NOT SECURITION (B) SLOPES AREAS OF PERIODIC CONCENTRATED RUNGHY (CITCHES) OR NA AREA SHAT) WE GENTANDE SON LOVER AGREGATE COVER GORGEATE COVER GORGEATE COVER GORGEATE COVER GORGEATE COVER AND COMMENT SET STABLES OF PREVENTS MICE PREV		MULCHING		M	CONTROLS UNWANTED VEGETATION AND PRESERVES MOISTURE. PROVIDES COVER		
AGGREGATE COVER (AS) VESETATION CANNOT BE ESTABLISHED, PREVENTS MUD PROVIDE BEING RICKED UP PAVING (D) PROVIDES PERMANENT COVER ON PARMING LOTS AND ROADS OR OTHER AREAS (R) PROVIDES PERMANENT COVER ON PARMING LOTS AND ROADS OR OTHER AREAS (R) TYPICALLY USED AREAS (D) TRUCKLY USED AREAS (D) TYPICALLY USED AREAS (D) TYPICAL			X	EB	SLOPES, AREAS OF PERIODIC CONCENTRATED RUNOFF (DITCHES) OR IN AREAS THAT	X	
ROGE DIVERSION ROGERATION DIVERSION DI CONTROLLO DIVERSION DIVERSION DIVERSION DIVERSION DIVERSION DIVE	SOIL COVER	AGGREGATE COVER		AG	VEGETATION CANNOT BE ESTABLISHED. PREVENTS MUD FROM BEING PICKED UP		
DIMERSIONS DIVERSIONS DIVERS DIVERSIONS DIVERS DIVERSIONS DIVERSIONS DIVERSIONS DIVERSIONS DIVERSIONS DI		PAVING		P			
DIVERSIONS COMBINATION DIVERSION COMBINATION DIVERSION CURB AND GUTTER COMPANDE DIVERSION CURB AND GUTTER COMPANDE DIVERSION CORRECTION COMPANDE DIVERSION CO		RIDGE DIVERSION		RD	TYPICALLY USED ABOVE SLOPES. USED WHERE AN EXCESS OF SOIL IS AVAILABLE.		
DIVERSIONS CURB AND GUTTER CURB AND GUTTER COFFERDAM COFFERDAM		CHANNEL DIVERSION		(CD)			
CURB AND GUTTER COO SPECUAL CASE OF DIVERSION USED IN CONJUNCTION WITH A STREET TO DIVERT WATER FROM AN ADEA NEEDON POTOCICION. BENCHES BENCHES BENCHES BENCHES BENCHES BENCHES COFFERDAM COO SPECUAL CASE OF DIVERSION CONSTRUCTED WHEN WORKING ON CUT SLOPES TO WATER FROM AN AREA NEEDON POTOCIC AND OB SOPE STABILITY. COFFERDAM COO STRUCTURAL DIVERSION OF WATER FOR CONSTRUCTION IN FLOWING WATER. BARE CHANNEL BENCHES BENCHES BENCHES BENCHES BARE CHANNEL COO PROVIDES MEANS OF CONVEYING RUNOFF TO DESIRED LOCATION. MAY BE USED TO DRAW DEPRESSIONAL AREAS. ONLY APPLICABLE WHEN VECOCITY OF FLOW IS VERY DOWN. STRUCTURAL STREAMBANK (SS) PROTECTS STREAMBANGS FROM EROSIVE FORCE OF FLOWING WATER. STRUCTURAL STREAMBANK (SS) PROTECTS STREAMBANGS FROM EROSIVE FORCE OF FLOWING WATER. PROVIDED ADDED STABILITY TO CHANNEL. USED WHEN VELOCITY OF FLOW IS NOT EXTREMELY FAST. WEGETATIVE STREAMBANK (SS) PROTECTS STREAMBANGS FROM EROSIVE FORCE OF FLOWING WATER AND THE STREAMBANK (STABILIZATION) LILIBED CHANNEL STREAMBANK SEWER STORM SEWER STORM SEWER STORM SEWER STORM SEWER STREAMBANK SEWER STORM SEWER STREAMBANK SE	DIVEDOIONO	COMBINATION DIVERSION		(DC)			
SHORTEN LENGTH OF SLOPE AND ADD SLOPE STABILITY. COFFERDAM (D) STRUCTURAL DIVERSION OF WATER FOR CONSTRUCTION IN FLOWING WATER. BARE CHANNEL (BC) DRAIN DEPRESSIONAL AREAS. ONLY APPLICABLE WHEN VELOCITY OF FLOW IS VERY LOW. STRUCTURAL STREAMBANK (SS) PROTECTS STREAMBANKS FROM EROSIVE FORCE OF FLOWING WATER. STREAMBANK (STABILZATION) WATERWAYS VEGETATIVE CHANNEL (VC) PROVIDED ADDED STABILITY TO CHANNEL. USED WHEN VELOCITY OF FLOW IS NOT LEXTREAMBANK STREAMBANK STREAMBANK STREAMBANK STREAMBANK STREAMBANK STREAMBANK STREAMBANK (SPROM EROSIVE FORCE OF FLOWING WATER. STREAMBANK STREAMBANK STREAMBANK STREAMBANK (SPROM EROSIVE FORCE OF FLOWING WATER AND PROVIDES NATURAL PLEASING APPEARANCE. VEGETATIVE CHANNEL (LINED WHEN VEGETATION WILL NOT PROTECT THE CHANNEL AGAINST HIGH VELOCITY OF WATER IN A DITCH TO NIMIMAZE SOIL. ENCLOSED DITCH CHECKS (D) LINED WHEN VEGETATION OF WHERE VEGETATION FOR WATER IN A DITCH TO NIMIMAZE SOIL. ENCLOSED DITCH CHECKS (D) LINED WHEN VEGETATION OF WHERE VEGETATION FOR WATER IN A DITCH TO NIMIMAZE SOIL. ENCLOSED DRAIN SEWER (S) SAME AS HERE STREAMBAND SEABLETY, USBOT OF CARRY BASE FLOW IN WATERWAYS AND TO LOWER WATER TABLE AND INTERCEPT GROUNDWATER FOR BETTER DROPN INLET SPILLWAY WERR SPILLWAY WERR SPILLWAY (M) DISSE FOR RELATIVELY SMALL VERTICAL DROPS AND SMALL FLOWS OF WATER. DOWN INLET WERR SPELLWAYS (S) SAME AS HIPE SPILLWAY EXCEPT LARGER FLOWS AND LARGE VERTICAL DROPS CAN BE ACCOMMODATED BOX INLET WERR SPILLWAYS (S) SAME AS WERE SPILLWAY EXCEPT LARGER FLOWS AND FLOWS MUCH GREATER THAN PIPE STRUCTURES. (S) SAME AS WERE SPILLWAY EXCEPT LARGER FLOWS AND FLOWS MUCH GREATER THAN PIPE STRUCTURES. (S) SAME AS WERE SPILLWAY EXCEPT LARGER FLOWS CAN BE ACCOMMODATED BOX INLET WERR SPELLWAYS (S) SAME AS WERE SPILLWAY EXCEPT LARGER FLOWS AND FLOWS MUCH GREATER THAN PIPE STRUCTURES. SAME AS WERS PRILWAY EXCEPT LARGER FLOWS AND FLOWS MUCH GREATER THAN PIPE S	DIVERSIONS	CURB AND GUTTER		(G)			
BARE CHANNEL BOPPONIDES MEANS OF CONVEYING RUNOFF TO DESIRED LOCATION, MAY BE USED TO DOWN DEFREESSONAL AREAS, ONLY APPLICABLE WHEN VELOCITY OF FLOW IS VERY LOW. STRUCTURAL STREAMBANK S		BENCHES		В			
BARE CHANNEL (BC) DIRAIN DEPRESSIONAL AREAS, ONLY APPLICABLE WHEN VELOCITY OF FLOW IS VERY LOW. STRUCTURAL STREAMBANK STABILIZATION VEGETATIVE CHANNEL VEGETATIVE STREAMBANK STROM EROSIVE FORCE OF FLOWING WATER AND PROVIDED ADDED STABILITY TO CHANNEL USED WHEN VELOCITY OF FLOW IS NOT EXTREAMBANK STROM EROSIVE FORCE OF FLOWING WATER AND PROVIDED AND ADDED STABILITY TO CHANNEL USED WHEN VELOCITIES OF FLOW OR WHERE VEGETATION CANNOT BE ESTABLISHED. UNDER CHANNEL UNDER CHANNEL UNDER CHANNEL UNDER CHANNEL UNDER STORM SEWER S		COFFERDAM		(CD)	STRUCTURAL DIVERSION OF WATER FOR CONSTRUCTION IN FLOWING WATER.		
STREAMBANK STREAMBANK WATERWAYS WEGETATIVE CHANNEL VEGETATIVE OF WATER AND AND THE CHANNEL AGAINST HIGH VEGETATIVE OF WATER AND ADTICATIVE OF WATER IN A DITCH TO MINIMIZE SOIL EROSION PRIOR TO THE DITCH BEING VEGETATED. STORM SEWER STORM SEWER STORM SEWER STRAIGHT PIPE SPILLWAY VEGETATIVE WATER TABLE AND INTERCEPT GROUNDWATER FOR BETTER VEGETATIVE OR GROWTH AND SLOPE STABILITY. USED TO ACRY BASE FLOW IN WATERWAYS AND TO DEWATER TABLE AND INTERCEPT GROUNDWATER FOR BETTER VEGETATIVE OR GROWTH AND SLOPE STABILITY. USED TO ACRY BASE FLOW IN WATERWAYS AND TO DEWATER SEDIMENT BASINS. SAME AS PIPE SPILLWAY WERE STRUCTURES. SAME AS WERE SPILLWAY EXCEPT LARGER FLOWS AND LARGE VERTICAL DROPS CAN BE ACCOMMODATED BECAUSE OF LOWER WERE REGITATIVE. SEDIMENT BASINS EMBANNAMENT SEDIMENT BASINS EMBANNAMENT SEDIMENT SEDIMENT FILE SEDIMENT SEDIMENT FILE SEDIMENT FILE SEDIMENT SED		BARE CHANNEL		ВС	DRAIN DEPRESSIONAL AREAS. ONLY APPLICABLE WHEN VELOCITY OF FLOW IS VERY		
WATERWAYS VECETATIVE STEAMBANK DITCH CHECKS DITCH CHECKS DITCH CHECKS DITCH CHECKS DITCH CHECKS SO USED IN DITCHES TO RETARD THE VELOCITY OF WATER IN A DITCH TO MINIMIZE SOIL ENCLOSED DRAINAGE ENCLOSED DRAINAGE UNDERDRAIN STORM SEWER STRAIGHT PIPE SPILLWAY SS USED FOR RELATIVELY SMALL VERTICAL DROPS AND SMALL FLOWS OF WATER. DROP NILET SPILLWAY WE SEED FOR RELATIVELY SMALL VERTICAL DROPS AND SMALL FLOWS OF WATER. BOX INLET WER SPILLWAY SSED FOR RELATIVELY SMALL VERTICAL DROPS AND FLOWS MUCH GREATER THAN PIPE STRUCTURES. SAME AS RIPE SPILLWAY EXCEPT LARGER FLOWS AND LARGE VERTICAL DROPS CAN BE ACCOMMODATED. BE ACCOMM	WATERWAYS	STREAMBANK		(SSS)	PROTECTS STREAMBANKS FROM EROSIVE FORCE OF FLOWING WATER.		
VEGETATIVE STREAMBANK STABILIZATION STREAMBANK STABILIZATION CITY OF PROVIDES ANTURAL, PLEASING APPEARANCE, PROVIDES ANTURAL, PLEASING AND APPEARANCE, PROVIDES ANTURAL, PLEASING, PL		VEGETATIVE CHANNEL		(vc)			
DITCH CHECKS SDD USED IN DITCHES TO RETARD THE VELOCITY OF WATER IN A DITCH TO MINIMIZE SOIL ENCLOSED DRAINAGE STORM SEWER STORM SE		STREAMBANK		(vs)			
STORM SEWER STRAIGHT PIPE SPILLWAY STORM SEWER SPILLWAY STRAIGHT PIPE SPILLWAY STORM SEWER SPILLWAY STRAIGHT PIPE SPILLWAY STRAIL SAND SMAIL VERTICAL DROPS AND STRAILT SAND SMAIL FLOWS OF WATER STRAIL SAND SMAIL VERTICAL DROPS AND SMAIL SECTION STRAIGHT PASSED TO DESCRIPT STRAILT SAND STRAIGHT SAND SAND SAND STRAIGHT SAND SAND SAND SAND SAND SAND SAND SAND		LINED CHANNEL		(rc)			
ENCLOSED DRAINAGE UNDERDRAIN STRAIGHT PIPE SPILLWAY SS) USED FOR RELATIVELY SMALL VERTICAL DROPS AND SMALL FLOWS OF WATER. BOAD INLET SPILLWAY WER SPILLWAY WER SPILLWAY WER SPILLWAY USED FOR RELATIVELY SMALL VERTICAL DROPS AND SMALL FLOWS OF WATER. BOAD INLET WEIR SPILLWAY WERS SPILLWAY USED FOR RELATIVELY SMALL VERTICAL DROPS AND FLOWS MUCH GREATER THAN PIPE STRUCTURES. BOAD INLET WEIR SPILLWAY BOAD INLET SPILLWAY BO		DITCH CHECKS		(SDC)			
UNDERDRAIN STRAIGHT PIPE SPILLWAY STRAIGHT PIPE SPILLWAY OROP INLET SPILLWAY OROP INLET SPILLWAY WER SPILLWAY WER SPILLWAY WER SPILLWAY USED FOR RELATIVELY SMALL VERTICAL DROPS AND SMALL FLOWS OF WATER. BOX INLET WEIR SPILLWAY WERS SPILLWAY BOX INLET WEIR SPILLWAY OUTLETS LINED APRON EMBANKMENT SEDIMENT BASINS SEDIMENT BASINS SEDIMENT BASINS SEDIMENT BASINS SEDIMENT FILLER OF USED WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. COMBINATION SEDIMENT BASIN SEDIMENT FILTERS FILTER BARRIER FILTER OF USED WHEN EXCESS EARTH FILL IS NOT AVAILABLE. OUT OF THE SEDIMENT FROM RUNOFF. USED WHEN EXCESS EARTH FILL IS NOT AVAILABLE. FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGEWAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED FOR ROADWAY CURB INLETS. SILT FENCE OF USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. TREATMENCE FILTER SEDIMENT FROM BEING PICKED UP AND CARRIED OFF-SITE. DUST AND TRAFFIC USED ALONG DRAINAGE ONSTRUCTION SITE	ENCLOSED	STORM SEWER		(ST)			
SPILLWAYS SPILLWAY DROP INLET SPILLWAY WEIR SPILLWAY WEIR SPILLWAY WEIR SPILLWAY WEIR SPILLWAY WUSED FOR RELATIVELY SMALL VERTICAL DROPS AND FLOWS MUCH GREATER THAN PIPE STRUCTURES. BOX INLET WEIR SPILLWAY BOX INLET WEIR SPILLWAY BOX INLET WEIR SPILLWAY BOX INLET WEIR SPILLWAY BE SAME AS WEIR SPILLWAY EXCEPT LARGER FLOWS CAN BE ACCOMMODATED BECAUSE OF LOWER WEIR LENGTH. CUTLETS LINED APRON LA PROTECTS DOWNSTREAM CHANNEL FROM HIGH VELOCITY OF FLOW DISCHARGING FROM STRUCTURES. SEDIMENT BASINS EXCAVATED SEDIMENT BASIN EXCAVATED SEDIMENT BASIN COMBINATION SEDIMENT BASIN SEDIMENT FILTER BARRIER FILTER BF USED WHER TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. COMBINATION SEDIMENT BASIN COMBINATION SEDIMENT BASIN SEDIMENT FILTER BARRIER FILTER BF USED WHEN TOPOGRAPHY IS SUITABLE BUT ADDITIONAL CAPACITY IS NEEDED. BARRIER FILTER WE GETATIVE FILTER VF USED ALONG DRAINAGEWAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SIZE MUST BE INCREASED IN PROPORTION TO DRAINAGE AREA. FILTER FABRIC FILTER FABRIC FILTER FABRIC FF USED FOR ROADWAY CURB INLETS. INLET FILTER SILT FENCE SF USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SIZE MUST BE INCREASED IN PROPORTION TO DRAINAGE AREA. SILT FENCE SF USED JALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SILT FENCE SF USED JALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SILT FENCE SF USED JALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FLOCCULATION AND DEPOSITION PRIOR TO DISCHARGE. POLYMER TREATMENT POLYMER TREATMENT TO SUSTEMENT FROM LEAVING CONSTRUCTION SITE		UNDERDRAIN		UĐ	VEGETATION GROWTH AND SLOPE STABILITY. USED TO CARRY BASE FLOW IN		
SPILLWAYS WEIR SPILLWAY BECAUSE OF LOWER WEIR LENGTH. BOX INLET WEIR SPILLWAY BECAUSE OF LOWER WEIR LENGTH. WEIR SPILLWAY BECAUSE OF LOWER WEIR LENGTH. BECAUSE OF LOWER WEIR LENGTH. WEIR SPILLWAY BECAUSE OF LOWER WEIR LENGTH. BECAUSE OF LOWER WEIR LENGTH. WEIR SPILLWAY BOX INLET WEIR SCHOMED AND WISCHARGING FROM STRUCTURES. WEIR SPILLWAY BOX INLET WEIR SCHOMED AND WISCHARGING FROM STRUCTURES. WESD WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. SEDIMENT BASIN SEDIMENT BASIN WISC WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. WISC WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. SUSED WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. SUSED WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. SUSED WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. WEIR SPILLWAY WEIR SEMILE FROM HIGH VELOCITY OF FLOW DISCHARGING WEIR SPILLWAY WEIR S		STRAIGHT PIPE SPILLWAY		(SS)	USED FOR RELATIVELY SMALL VERTICAL DROPS AND SMALL FLOWS OF WATER.		
WEIR SPILLWAY WEIR SPILLWAY WEIR SPILLWAY BOX INLET WEIR SPILLWAY BS SAME AS WEIR SPILLWAY EXCEPT LARGER FLOWS CAN BE ACCOMMODATED BECAUSE OF LOWER WEIR LENGTH. OUTLETS LINED APRON EMBANKMENT SEDIMENT BASIN SEDIMENT BASIN EXCAVATED SEDIMENT BASIN EXCAVATED SEDIMENT BASIN BARRIER FILTER BARRIER FILTER BARRIER FILTER BE DISCAVATED SEDIMENT FILTERS FILTER FABRIC FILTER FABRIC FILTER FABRIC FILTER FABRIC FILTER FABRIC FILTER SILT FENCE POLYMER TREATMENT POLYMER TREATMENT MUD AND DON'S SAME AS WEIR SPILLWAY EXCEPT LARGER FLOWS CAN BE ACCOMMODATED BECAUSE OF LOWER WEIR LENGTH. BSEDIMENT FILTERS BASIN SEDIMENT FILTER BE OVERTHER FILTER BF USED WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE. SEDIMENT FILL IS NOT AVAILABLE. SEDIMENT FORM RUNOFF. USED WHERE TOPOGRAPHY IS SUITABLE BUT ADDITIONAL CAPACITY IS NEEDED. BARRIER FILTER BF USED TO FILTER SEDIMENT FROM RUNOFF. USED ALONG DRAINAGEWAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SIZE MUST BE INCREASED IN PROPORTION TO DRAINAGE AREA. FILTER FABRIC F		DROP INLET SPILLWAY		DIS			
OUTLETS LINED APRON EMBANKMENT SEDIMENT BASIN SEDIMENT BASIN EXACATED SEDIMENT BASIN AND EXACATED SEDIMENT FROM RUNOFF. EXECUTE BASIN EXACATED SEDIMENT FROM RUNOFF. EXECUTE BASIN BASI	SPILLWAYS	WEIR SPILLWAY		W			
SEDIMENT FILTER SEDIMENT FILTER SEDIMENT FROM RUNOFF. SEDIMEN				BS			
SEDIMENT BASIN EXCAVATED SEDIMENT BASIN EXCAVATED SEDIMENT BASIN COMBINATION SEDIMENT BASIN EXCAVATED SEDIMENT FAILURE AND WHEN EXCESS EARTH FILL IS NOT AVAILABLE. COMBINATION SEDIMENT BASIN EXCAVATED SEDIMENT FAILURE AND WHEN EXCESS EARTH FILL IS NOT AVAILABLE. EXCAVATED SEDIMENT FAILURE AND WHEN EXCESS EARTH FILL IS NOT AVAILABLE. EXCAVATED SEDIMENT BASIN EXCAVATED SEDIMENT BASIN EXCAVATED SEDIMENT BASIN OF AVAILABLE. EXCAVATED SEDIMENT BASIN OF AVAILABLE. EXCAVATED SEDIMENT BASIN OF AVAILABLE. EXCAVATED SEDIMENT FAILURE AND WHEN EXCESS EARTH FILL IS NOT AVAILABLE. EXCAVATED SEDIMENT FAILURE AND WHEN EXCESS EARTH FILL IS NOT AVAILABLE. EXCAVATED SEDIMENT FOOM RUNOFF. EXCAVATED SEDIMENT FROM RUNOFF. EXCAVATED SEDI	OUTLETS	LINED APRON		(LA)			Г
BASINS BASIN COMBINATION SEDIMENT BASIN COMBINATION SEDIMENT BASIN COMBINATION SEDIMENT BASIN BARRIER FILTER BE USED TO FILTER SEDIMENT FROM RUNOFF. VEGETATIVE FILTER VF USED ALONG DRAINAGEWAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SIZE MUST BE INCREASED IN PROPORTION TO DRAINAGE AREA. FILTERS FILTER FILTER FILTER FILTER INLET FILTER FILTER SILT FENCE POLYMER TREATMENT FILTER FILTE		EMBANKMENT SEDIMENT BASIN		(ES)	USED WHERE TOPOGRAPHY LENDS ITSELF TO CONSTRUCTING A DAM AND EARTH FILL IS AVAILABLE.		T
COMBINATION SEDIMENT BASIN CS USED WHEN TOPOGRAPHY IS SUITABLE BUT ADDITIONAL CAPACITY IS NEEDED. BARRIER FILTER BB USED TO FILTER SEDIMENT FROM RUNOFF. VEGETATIVE FILTER VF) USED ALONG DRAINAGEWAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SIZE MUST BE INCREASED IN PROPORTION TO DRAINAGE AREA. FILTERS FILTER FABRIC FF) USED FOR ROADWAY CURB INLETS. INLET FILTER INLET FILTER VF) INSERTED INTO CATCHBASINS AND INLETS WITH OPEN GRATES. SILT FENCE SILT FENCE POLYMER TREATMENT PT TREATMENT OF WATER WITH ANIONIC POLYACRYLAMIDE TO CAUSE SEDIMENT FLOCCULATION AND DEPOSITION PRIOR TO DISCHARGE. STABILIZED CONST. ENTRANCE DUST AND TRAFFIC DUST AND TRAFFIC OT PREVENTS MUST FROM LEAVING CONSTRUCTION SITE		EXCAVATED SEDIMENT		(xs)			
BARRIER FILTER WEGETATIVE FILTER VEGETATIVE FILTER VEGETATIVE FILTER VEGETATIVE FILTER VEGETATIVE FILTER VEGETATIVE FILTER VEGETATIVE FILTER VF) USED ALONG DRAINAGEWAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. SIZE MUST BE INCREASED IN PROPORTION TO DRAINAGE AREA. FILTER FABRIC FF) USED FOR ROADWAY CURB INLETS. INLET FILTER VIF) INSERTED INTO CATCHBASINS AND INLETS WITH OPEN GRATES. SILT FENCE SILT FENCE POLYMER TREATMENT P) TREATMENT OF WATER WITH ANIONIC POLYACRYLAMIDE TO CAUSE SEDIMENT FLOCCULATION AND DEPOSITION PRIOR TO DISCHARGE. STABILIZED CONST. ENTRANCE DUST AND TRAFFIC DUST AND TRAFFIC DUST AND TRAFFIC VEGETATIVE FILTER SEDIMENT FROM RUNOFF. VISED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. STABILIZED CONST. STABILIZED CONST. ENTRANCE DUST AND TRAFFIC DUST AND TRAFFIC DUST AND TRAFFIC VEGETATIVE FILTER SEDIMENT FROM RUNOFF. VISED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. STABILIZED CONST. STABILIZED CONST. ENTRANCE DUST AND TRAFFIC	2/101110	COMBINATION SEDIMENT		(cs)			
SEDIMENT FILTER				(BF)	USED TO FILTER SEDIMENT FROM RUNOFF.		Т
FILTER FABRIC FILTER FABRIC FF USED FOR ROADWAY CURB INLETS. INLET FILTER INLET FILTER INLET FILTER INSERTED INTO CATCHBASINS AND INLETS WITH OPEN GRATES. SILT FENCE SILT FENCE POLYMER TREATMENT FILTER FABRIC FF USED FOR ROADWAY CURB INLETS. INSERTED INTO CATCHBASINS AND INLETS WITH OPEN GRATES. SILT FENCE SF USED ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. POLYMER TREATMENT POLYMER TREATMENT FLOCCULATION AND DEPOSITION PRIOR TO DISCHARGE. STABILIZED CONST. ENTRANCE STABILIZED CONST. ENTRANCE DUST AND TRAFFIC PREVENTS DUST FROM LEAVING CONSTRUCTION SITE		VEGETATIVE FILTER		(VF)			T
INLET FILTER INSERTED INTO CATCHBASINS AND INLETS WITH OPEN GRATES. SILT FENCE SILT FENCE POLYMER TREATMENT POLYMER TREATMENT STABILIZED CONST. ENTRANCE STABILIZED CONST. ENTRANCE DUST ALONG DRAINAGE WAYS OR PROPERTY LINES TO FILTER SEDIMENT FROM RUNOFF. TREATMENT OF WATER WITH ANIONIC POLYACRYLAMIDE TO CAUSE SEDIMENT FLOCCULATION AND DEPOSITION PRIOR TO DISCHARGE. STABILIZED CONST. ENTRANCE DUST AND TRAFFIC	MULCHING MULCHING MULCHING MULCHING MUCCONTROLS MONOWHERE VEGET PROTECTS AN SLOPES, AREA MAY BE DAMAA AGGREGATE COVER AGDEDIVERSION (D) TYPICALLY US AVAILABLE. TYPICALLY US SHORTEN LEN WATERWAY BERCIAL CASE SHORTEN LEN WATERWAYS FROVIDES ME SHORTEN LEN UNGETATIVE CHANNEL VEGETATIVE CHANNEL VEGETATIVE CHANNEL VEGETATIVE CHANNEL VEGETATIVE CHANNEL VEGETATIVE CHANNEL VEGETATIVE STREAMBANK STABILIZATION VEGETATIVE STREAMBANK STABILIZATION VEGETATIVE TYPICALLY US STRUCTURAL SSS) PROVIDES ME PROVIDES ME PROVIDES ME SHORTEN LEN STRUCTURAL SSS) PROTECTS STI PROVIDES ME PROVIDES ME STRUCTURAL SSS) PROTECTS STI PROVIDES ME STRUCTURAL SSS) PROTECTS STI PROVIDES ME STRUCTURAL STRUCTURAL STRUCTURAL STRUCTURAL STRUCTURAL STRUCTURAL STRUCTURAL STRUCTURAL STRUCTURAL SSS) SPECIAL CASE SHORTER FROM SSS) SPECIAL CASE SHORTER FROM SSS) SPECIAL CASE SHORTER FROM SSS) PROTECTS STI SPECIAL CASE SODIAL STRUCTURAL STRUCTURAL STRUCTURAL STRUCTURAL ST						
SILT FENCE SILT FENCE POLYMER TREATMENT POLYMER TREATMENT POLYMER TREATMENT POLYMER TREATMENT PI TREATMENT OF WATER WITH ANIONIC POLYACRYLAMIDE TO CAUSE SEDIMENT FLOCCULATION AND DEPOSITION PRIOR TO DISCHARGE. STABILIZED CONST. ENTRANCE SE PREVENTS MUD FROM BEING PICKED UP AND CARRIED OFF-SITE. DUST AND TRAFFIC DUST AND TRAFFIC DUST AND TRAFFIC		INLET FILTER	X	(F)	INSERTED INTO CATCHBASINS AND INLETS WITH OPEN GRATES.	X	
POLYMER TREATMENT POLYMER TREATMENT PT TREATMENT OF WATER WITH ANIONIC POLYACRYLAMIDE TO CAUSE SEDIMENT FLOCCULATION AND DEPOSITION PRIOR TO DISCHARGE. STABILIZED CONST. ENTRANCE SE PREVENTS MUD FROM BEING PICKED UP AND CARRIED OFF-SITE. DUST AND TRAFFIC DUST AND TRAFFIC DUST AND TRAFFIC DIST EPOM LEAVING CONSTRUCTION SITE		SILT FENCE		(SF)			
MUD AND DUST CONTROL MUD AND DUST CONTROL MUD AND DUST AND TRAFFIC		POLYMER TREATMENT		PT	TREATMENT OF WATER WITH ANIONIC POLYACRYLAMIDE TO CAUSE SEDIMENT		Т
CONTROL DUST AND TRAFFIC DUST EDOM LEAVING CONSTRUCTION SITE				SE			
	DIVERSIONS DIVERSIONS WATERWAYS ENCLOSED DRAINAGE SPILLWAYS OUTLETS SEDIMENT BASINS MUD AND DUST		X	(TO	PREVENTS DUST FROM LEAVING CONSTRUCTION SITE.	X	

CONSTRUCTION STAGING: LONG BEACH ROAD SIDEWALK IMPROVEMENTS PROJECT

PRF - CONSTRUCTION

- INSTALL PREVENTATIVE EROSION CONTROL MEASURES INCLUDING INLET FILTERS.

CONSTRUCTION

- 1. REMOVE CURB AND GUTTER, CURB, SIDEWALK, AND DRIVEWAYS.
- 2. CONSTRUCT CURB AND GUTTER AND CURB.
- 3. EXCAVATE FOR WIDENED SIDEWALK AND CONSTRUCT SIDEWALK.
- 4. EXCAVATE FOR DRIVEWAYS AND CONSTRUCT DRIVEWAYS.
- RESTORE ALL AREAS OF DISTURBANCE WITH TOPSOIL, SEED, AND EROSION CONTROL BLANKET.
- 6. REMOVE ALL TEMPORARY EROSION CONTROL MEASURES FROM THE SITE.

CONSTRUCTION STAGING NOTES:

THE CONTRACTOR WILL NOT BE ALLOWED TO CLEAR MORE THAN ONE STAGE AT A TIME. STABILIZATION OF DISTURBED AREAS MUST BE INITIATED WITHIN 1 WORKING DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES AND SHALL BE COPMILETED AS SOON AS POSSIBLE BUT NOT LATER THAN 14 DAYS FROM THE INITIATION OF THE STABILIZATION WORK IN AN AREA. PERMANENT SOIL STABILIZATION SHALL BE INSTALLED PRIOR TO STARTING THE NEXT STAGE OF CONSTRUCTION.

IT IS ANTICIPATYED THAT THERE WILL BE NO WINTER SHUT DOWN.

SOIL PROTECTION SCHEDULE

STABILIZATION TYPE	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	ост.	NOV.	DEC.
PERMANENT SEEDING				Α				A				
DORMANT SEEDING	В										_B	
TEMPORARY SEEDING			<u>,c</u>				D					
MULCHING -	E											_
Wolching												

- A. IDOT SEED MIX CLASS 1A 180 LBS/ACRE
- B. INCREASE SEEDING RATES BY 25% WHEN DORMANT SEEDING
- C. SPRING OATS 100 LBS/ACRE
- D. WHEAT OR CEREAL RYE 150 LBS/ACRE.
- E. HYDRAULIC MULCH 750 LBS AND 1000 GAL OF WATER PER ACRE

INSPECTION AND MAINTENANCE TABLE

ACTIVITY	RESPONSIBLE PARTY	DURATION
MAINTENANCE OF STABILIZATION DURING CONSTRUCTION		DURING CONSTRUCTION AS NEEDED
OBSERVATION OF STABILIZATION DURING CONSTRUCTION		WEEKLY AND W/IN 24 HRS AFTER RAINFALL EVENT OF 0.5" OR GREATER
VEGETATION MAINTENANCE		1 YEAR FROM COMPLETION
VEGETATION AND STABILIZATION MAINTENANCE		ONGOING FROM PROJECT COMPLETION

CONTRACTOR CERTIFICATION

CONTRACTOR CERTIFICATION

"I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION"

BEATH LEB NOT THAT OF THE			
GENERAL CONTRACTOR			
SIGNATURE	TITLE	DATE	
COMPANY		-	
SUB-CONTRACTOR RESP	ONSIBLE FOR:		_
SIGNATURE	TITLE	DATE	
COMPANY		-	
WITNESSED BY OWNER			
SIGNATURE	TITLE	DATE	
COMPANY		-	

THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL GENERAL AND SPECIAL REQUIREMENTS, CONDITIONS, AND PROVISIONS OR ALL APPLICABLE LOCAL, STATE, AND FEDERAL PERMITS ISSUED FOR THIS PROJECT.

WBK ENGINEERING, LLC IS NOT RESPONSIBLE FOR IMPLEMENTATION OF THE STORMWATER POLLUTION PREVENTION PLAN, INCLUDING MAINTENANCE AND/OR REPAIR OF SOIL EROSION AND SEDIMENT CONTROL MEASURES, OR FOR COMPLIANCE OF THE CONTRACTORS (AND SUB-CONTRACTORS) WITH THE GENERAL NPDES PERMIT FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

- 2 6 4 3 9 7 8

STORMWATER POLLUTION PREVENTION

LONG BEACH ROAD SIDEWALK PROGRAM

CLIENT

WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755




PROJECT NO. 21-0123


DATE: 03/28/2022


DRAWING NO. **SW2**

SHEET

38 OF 58








DETAIL 1

DETAIL 2

DETAIL 3




NOTES:

- 1. Staples shall be placed in a diamond pattern at 2 per s.y. for stiched blankets. Non—stiched shall use 4 staples per s.y. of material. This equates to 200 staples with stiched blanket and 400 stapels with non-stiched blanket per 100 s.y. of material.
- 2. Staple or push pin lengths shall be selected based on soil type and conditions. (minimum staple length is 6")
- 3. Erosion control material shall be placed in contact with the soil over a prepared seedbed.
- 4. All anchor slots shall be stapled at approximately 12" intervals.

EROSION CONTROL BLANKET INSTALLATION DETAILS

	Date
JOHNSON	11/08

AUTOCAD2006



DATE = 3/28/3 NAME = ssunda NAME = 7:\202

DRAWING NO. EC1 SHEET


PROJECT NO. 21-0123 DATE: 03/28/2022

LONG BEACH ROAD SIDEWALK PROGRAM

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, LLC 116 WEST MAIN STRET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

EROSION CONTROL DETAILS



DATE ::

SIDEWALK PROGRAM
EROSION CONTROL
DETAILS OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

CLIENT :


WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755



PROJECT NO. 21-0123

DATE: 03/28/2022

DRAWING NO. EC2



- 2 E 4 3 C 7 8 OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

CONSTRUCTION DETAILS


THE LONG BEACH ROAD SIDEWALK PROGRAM

WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755



PROJECT NO. 21-0123 DATE: 03/28/2022 DRAWING NO. DT1

SHEET 41 OF 58



LOT DATE = 3/28/2022 SER NAME = ssundoreson TLE NAME = 2:\2021\210123 LoneBeachRdSidewo

DRAWING NO. DOT1
SHEET

LONG BEACH ROAD SIDEWALK PROGRAM

1 2 8 4 3 2 7


OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

> WBK ENGINEERING, L 116 WEST MAIN STREET, SUITE 20 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

42 OF 58

PROJECT NO. 21-0123

DATE: 03/28/2022



DATE

SHEET


OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, L 116 WEST MAIN STRET, SUITE 20 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

WBK S

LONG BEACH ROAD SIDEWALK PROGRAM

IDOT HIGHWAY STANDARDS



DATE

SS SIDEWALK PROGRAM

VOP IDOT HIGHWAY

STANDARDS

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543


.. Z

> WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

VBKENGINERING

PROJECT NO. 21-0123 DATE: 03/28/2022


DRAWING NO. DOT3



DATE = 3/28/2 NAME = ssunds NAME = Z:\202

45 OF 58

WBK ENGINEERING, LLC 116 WEST MAIN STRET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755



DATE ::

DRAWING NO. DOT5 SHEET

LONG BEACH ROAD SIDEWALK PROGRAM


1 2 8 4 3 2 7

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, L 116 WEST MAIN STREET, SUITE 20 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

46 OF 58


PROJECT NO. 21-0123 DATE: 03/28/2022



DATE = 3/28/2022 NAME = ssundarese NAME = 7:\2021\21

DRAWING NO. DOT6 47 OF 58

IDOT HIGHWAY STANDARDS



DATE :: NAME ::

SIDEWALK PROGRAM
IDOT HIGHWAY
STANDARDS

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

PROJECT NO. 21-0123 DATE: 03/28/2022

DRAWING NO. DOT7

POST MOUNTED SIGNS

** When curb or paved shoulder are present this dimension shall be 24 (600) to the face of curb or 6' (1.8 m) to the outside edge of the paved shoulder.


MAX WIDTH

MILES

AHEAD


W12-I103-4848

WIDTH RESTRICTION SIGN XX'-XX" width and X miles are variable.



SIGNS ON TEMPORARY SUPPORTS

*** When work operations exceed four days, this dimension shall be 5' (1.5 m) min. If located behind other devices, the height shall be sufficient to be seen completely above the devices.



HIGH LEVEL WARNING DEVICE

ROAD CONSTRUCTION NEXT X MILES

END CONSTRUCTION

G20-I104(0)-6036

G20-I105(0)-6024

LONG BEACH ROAD SIDEWALK PROGRAM

1 2 8 4 3 2 7

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543

WBK ENGINEERING, L 116 WEST MAIN STRET, SUITE 20 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

This signing is required for all projects 2 miles (3200 m) or more in length.

ROAD CONSTRUCTION NEXT X MILES sign shall be placed 500' (150 m) in advance of pro-

END CONSTRUCTION sign shall be erected at the end of the job unless another job is within 2 miles (3200 m).

Dual sign displays shall be utilized on multi-

WORK LIMIT SIGNING

WORK ZONE **SPEED** LIMIT PHOTO **ENFORCE**I

W21-III5(0)-3618

R2-1-3648

R10-I108p-3618 ****

SXXX FINE **MINIMUM**

R2-I106p-3618

Sign assembly as shown on Standards or as allowed by District Operations.

END WORK ZONE SPEED LIMIT

G20-I103-6036

This sign shall be used when the above sign assembly is used.

HIGHWAY CONSTRUCTION SPEED ZONE SIGNS

**** R10-I108p shall only be used along roadways under the juristiction of the State.


DEVICES


STANDARD 701901-08

TRAFFIC CONTROL

(Sheet 2 of 3)

Illinois Department of Transportation






FLAGGER TRAFFIC CONTROL SIGN

PROJECT NO. 21-0123 DATE: 03/28/2022 DRAWING NO. DOT8

SHEET

49 OF 58

DATE NAME



DATE :: NAME ::


SHEET

50 OF 58

WBK ENGINEERING, L 116 WEST MAIN STRET, SUITE 20 ST. CHARLES, ILLINOIS 60174 (630) 443-7755


WBK SENDENCE OF THE SENDENCE O

IDOT HIGHWAY STANDARDS



LOT DATE = 3/28/2022 SER NAME = ssundareson II.E NAME = 7:\2021\210123_L

SHEET




DATE ::

DRAWING NO. DOT1 SHEET

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543


WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755




DATE = 3/28/2 NAME = ssunda

PROJECT NO. 21-0123 DATE: 03/28/2022 DRAWING NO. DOT1:

WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755




DATE :: NAME ::



DATE = 3/28/2 NAME = ssunds

55 OF 58

IDOT HIGHWAY STANDARDS



2 x 2 x var. (51 x 51 var.) 1¾ x 1¾ x 12 (44 x 44 x 300) 2¼ x 2¼ x 60 (57 x 57 x 1500)

> 2½ x 2½ x 18 (64 x 64 x 450) 2¼ x 2¼ x 36) (57 x 57 x 900)

PAVEMENT MOUNT DETAIL

GENERAL NOTES

All bolts % (M10) hex head zinc or cadmium plated.

All dimensions are in inches (millimeters) unless otherwise shown.

		unic
DATE	REVISIONS	
1-1-09	Switched units to	
	English (metric).	
1-1-07	New Standard. Used to	_
	be part of Standard	
	720006.	
	<u> </u>	

SPLICE DETAIL

TELESCOPING STEEL SIGN SUPPORT

STANDARD 728001-01

Illinois Department of Transportation


GROUND MOUNT DETAIL

PROJECT NO. 21-0123 DATE: 03/28/2022 DRAWING NO. DOT1


WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

56 OF 58

DATE = 3/28/2 NAME = ssunda



TWO POST INSTALLATION




For diamond shaped sign with side S as shown, use required post size for a sign with W = 0.7Sand D = 1.4S.

Illinois Dep	partment of Tra	nsportat	ion
PASSED ———————————————————————————————————	January 1, #2534 X CY AND PROCEDURES	_ 2009	ISSUED
APPROVED	January 1, L 2/a_ GN AND ENVIRONMEN	_ 2009 T	1-1-97

ONE POST INSTALLATION

DEPTH (D) 18 (450)	5'-0" (1.5 m) 5'-6" (1.7 m) 6'-0" (1.8 m) 6'-6" (2.0 m)	12 (300) A A	18 (450) A	24 (600)	30 (750)	36
	5'-6" (1.7 m) 6'-0" (1.8 m) 6'-6" (2.0 m)	Α	Α		(130)	(900
	6'-0" (1.8 m) 6'-6" (2.0 m)	_		Α	Α	Α
	6'-6" (2.0 m)	Λ	Α	Α	Α	Α
		_ ^	Α	Α	Α	В
	=1 01 (O 4)	Α	Α	Α	Α	В
(430)	7' - 0" (2.1 m)	Α	Α	Α	Α	В
	7'-6" (2.3 m)	Α	Α	Α	Α	В
	8' -0" (2.4 m)	Α	Α	Α	Α	В
	8'-6" (2.6 m)	Α	Α	Α	В	В
	9' -0" (2.7 m)	Α	Α	Α	В	В
	5'-0" (1.5 m)	Α	Α	Α	Α	В
	5'-6" (1.7 m)	A	A	A	A	В
-	6'-0" (1.8 m)	A	A	A	В	В
ŀ	6'-6" (2.0 m)	A	A	A	В	В
24	7'-0" (2.1 m)	A	A	A	В	В
(600)	7'-6" (2.3 m)	A	A	A	В	В
ŀ	8'-0" (2.4 m)	A	A	A	В	2A
ŀ	8'-6" (2.6 m)	A	A	В	В	2A
	9'-0" (2.7 m)	A	A	В	В	2A
	5'-0" (1.5 m)	Α	Α	Α	В	В
	5'-6" (1.7 m)	Α	Α	Α	В	2A
	6'-0" (1.8 m)	Α	Α	Α	В	2A
30	6'-6" (2.0 m)	Α	Α	Α	В	2A
(750)	7'-0" (2.1 m)	Α	Α	В	В	2A
` '	7' -6" (2.3 m)	Α	Α	В	В	2A
	8'-0" (2.4 m)	Α	Α	В	В	2A
	8'-6" (2.6 m)	Α	Α	В	2A	2A
	9'-0" (2.7 m)	Α	Α	В	2A	2A
	5'-0" (1.5 m)	Α	Α	В	В	2A
	5'-6" (1.7 m)	Α	Α	В	В	2A
	6'-0" (1.8 m)	Α	Α	В	В	2A
2.0	6'-6" (2.0 m)	Α	Α	В	2A	2A
36 (900)	7'-0" (2.1 m)	Α	Α	В	2A	2A
(900)	7'-6" (2.3 m)	Α	Α	В	2A	2A
	8'-0" (2.4 m)	Α	В	В	2A	2A
	8'-6" (2.6 m)	Α	В	В	2A	2B
	9'-0" (2.7 m)	Α	В	2A	2A	2B
ı	5'-0" (1.5 m)	Α	А	В	2A	2A
}		A	В	В	2A 2A	2A 2A
}	5'-6" (1.7 m) 6'-0" (1.8 m)	A	В	В	2A 2A	2A 2A
}	6'-6" (2.0 m)	A	В	2A	2A 2A	2A 2B
4' -0"		A		2A 2A	2A 2A	2B
(1.2 m)		A	B B	2A 2A	2B	2B 2B
}		A	В	2A 2A	2B	2B 2B
	8'-0" (2.4 m) 8'-6" (2.6 m)	В	В	2A 2B	2B	2B 2B
	9'-0" (2.6 m)	В	2A	2B	2B	ZB



DETAIL OF MOUNTING SIGN TO POST

NOTE: Minimum of 2 bolts per post required.

GENERAL NOTES

DESIGN: Current AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals.

LOADING: for 60 mph (95 km/h) wind velocity with 30% gust factor, normal to sign.

SOIL PRESSURE: Minimum allowable soil pressure 1.25 tsf (120 kPa).

See Standard 720011 for details of Types A and B

All dimensions are in inches (millimeters)

		۵.
DATE	REVISIONS	
1-1-09	Switched units to	1
	English (metric).	
]
1-1-97	Renum. Standard 2363-2.	⊩
]
		1

APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

STANDARD 729001-01

WBK ENGINEERING, LLC 116 WEST MAIN STREET, SUITE 201 ST. CHARLES, ILLINOIS 60174 (630) 443-7755

OSWEGO TOWNSHIP ROAD DISTRICT 1150 ROUTE 25 OSWEGO, IL 60543


LONG BEACH ROAD SIDEWALK PROGRAM

IDOT HIGHWAY STANDARDS

PROJECT NO. 21-0123 DATE: 03/28/2022 DRAWING NO. DOT10

57 OF 58

DATE = 3/28/2 NAME = ssunda



DATE = 3/28/2 NAME = ssunder NAME = Z1/2021 DATE: 03/28/2022

DRAWING NO. **DOT1**SHEET

PROJECT NO. 21-0123